

Conditional Inference Trees and Forests for Feature Selection

Robert Milletich, Justin Downes, Steve Goley, Newel Hirst
Amazon Web Services
{rmilleti,jusdow,sgoley,nhirst}@amazon.com

Abstract

Conditional inference trees (CIT) and conditional inference forests (CIF) reduce split-selection bias by testing features before choosing split thresholds, but repeated permutation tests and threshold searches can make these methods computationally expensive. We study CIT and CIF as top- k feature-ranking methods for downstream prediction using real-data benchmarks, runtime ablations, and synthetic feature-recovery experiments. At a fixed node, if the features and permutation budget do not depend on the node responses, Bonferroni-corrected +1 Monte Carlo permutation p -values control nodewise rejection under the complete permutation null. CIF ties for 3rd among 17 classification methods on 21 datasets and ranks 2nd among 18 regression methods on 8 datasets. With Bonferroni correction held fixed, the CIF runtime ablations indicate that adaptive stopping and the number of thresholds searched have the largest measured effect on runtime: turning off adaptive stopping increases fitting time by $6.1\text{--}6.5\times$ on synthetic data and $483\text{--}717\times$ on real data, and exact threshold search by $1.1\text{--}21\times$, while downstream score changes are at most 0.010. Sparse high- p simulations indicate that forest feature sampling can leave informative features out of many split decisions. Overall, the results support CIF as a top- k feature-ranking method in the evaluated downstream prediction benchmarks.

1 Introduction

Conditional inference separates feature selection from threshold optimization to reduce split selection bias. Classical CART trees choose both a feature and a threshold from the same label-dependent search, which helps explain the well-documented preference for features with many admissible cutpoints [4, 23, 26, 27, 35, 37, 38]. In the conditional inference framework [17, 18], Stage A tests features for association with the response at the current node and selects among them; Stage B then optimizes a threshold within the selected feature. That separation addresses split selection bias, but the classical approach can require substantial computation through large permutation budgets and exhaustive threshold scans at every node. The same conditional inference framework also motivated later work on conditional variable importance [39]. A related line of work uses forests directly for variable screening and ranking, rather than only for final prediction [10].

This paper evaluates conditional inference trees (CIT) and conditional inference forests (CIF) as feature selection methods. For each seed and cross-validation fold, a method produces a ranking from the training fold. Fixed downstream learners are then fit on top- k prefixes of that ranking and evaluated on held-out data, with results summarized across datasets. The benchmark asks whether tree- and forest-derived rankings put predictive variables early enough to improve fixed downstream models. We also ask whether CIT/CIF runtime hyperparameters reduce computation while preserving ranking quality, and where CIF recovery is weaker in high- p or synthetic settings. This feature-selection benchmark is separate from work on trees and forests as direct predictors or causal estimators [1, 3, 42]. Because several methods have tunable configurations, the benchmark

chooses one configuration per method and task. As a sensitivity check, leave-one-dataset-out (LODO) analyses repeat the configuration choice after holding out each dataset, using the complete-case panels defined in Section 4.2.

The theorem studies the Stage A feature test at a fixed node. It assumes that the features tested at the node and the resample budget are fixed independently of the node responses, so exhaustive fixed- B p -values have a clear permutation reference distribution under the nodewise complete permutation null. The benchmarks then evaluate the tree and forest feature rankings empirically.

Contributions. This paper contributes a real-data benchmark of conditional-inference feature rankings for top- k downstream prediction. The benchmark compares CIF with ctree, cforest, CIT, and other baselines in classification and companion regression analyses, and includes ablations of the main CIT/CIF runtime hyperparameters. The paper also states the fixed-node, exhaustive fixed- B Stage A guarantee (Theorem 1 and Corollary 1); the full tree and forest rankings are evaluated in the benchmarks. Finally, the high- p and synthetic analyses show cases with weaker top- k recovery and how forest feature sampling can reduce how often forest splits use informative features (Section 6).

Version note. This version corrects five defects in the benchmark harness: the feature-index mapping used when passing data to the R ctree and cforest implementations, the seeding of cross-validation folds, the rank ordering returned by RF-RFE, the rank ordering returned by Boruta, and the correlation threshold used by conditional permutation importance. All benchmark results were regenerated from the corrected runs. The corrections move several comparators, most visibly RF-RFE, which now leads the classification comparison, while the conclusions about CIF are unchanged: CIF ties for 3rd of 17 classification methods and ranks 2nd of 18 regression methods.

2 Tree-growing method

At each internal node, conditional inference trees make two decisions. Stage A tests features for association with the response and chooses a feature to split. Stage B then searches thresholds only for that selected feature; if no valid split is accepted, the node becomes terminal. In this paper, CIT denotes the resulting single-tree feature selection method. CIF denotes a bootstrap ensemble of such trees with feature sampling at each node and feature rankings formed by aggregating split importances across trees. CIF-all disables feature subsampling: every nonconstant available feature can enter Stage A at each node. This changes the Stage A feature set, the Stage A multiplicity correction, and the per-node computational cost.

2.1 Stage A and Stage B

At a node t , write (X_t, Y_t) for the samples reaching that node. Let $F_{t,\text{avail}}$ be the feature set carried into the node by the tree-growing algorithm, including any feature muting inherited from ancestors. Let $F_{t,\text{nonconst}} \subseteq F_{t,\text{avail}}$ be the features that are nonconstant on the node samples. After any feature subsampling, Stage A considers a set $F_t \subseteq F_{t,\text{nonconst}}$; its size $m_t = |F_t|$ is the Bonferroni denominator for that node. Any label-independent auxiliary randomness used by a selector is denoted by U and is held fixed in the fixed-node guarantee.

When adaptive stopping is enabled during tree growing, Stage A can evaluate features sequentially and stop before every feature in F_t has been tested. Let $E_t \subseteq F_t$ denote the evaluated subset; in the exhaustive fixed- B reference rule, $E_t = F_t$. The fixed-node theorem in Section 3 applies to that

reference rule: the features in F_t and the budget B are fixed independently of the node responses, and every $p_{t,j}$ for $j \in F_t$ uses that budget. Adaptive tree growing adds response-dependent node selection, inherited feature muting, and stopping-time scores used for tree construction.

Stage A (feature selection). In the exhaustive fixed- B setting, Stage A follows the feature-selection and threshold-search separation of conditional inference trees [18]. The original conditional inference tests use the permutation-statistic framework of Strasser and Weber [36]; here, Monte Carlo label permutations calibrate the configured selector statistic. Stage A computes a selector statistic $T_j^{\text{sel}}(X_{t,j}, Y_t; U)$ and permutation p -value $p_{t,j}$ for every feature $j \in F_t$, then selects

$$p_t^{\star, \text{ref}} := \min_{j \in F_t} p_{t,j}, \quad M_t^{\star} := \{j \in F_t : p_{t,j} = p_t^{\star, \text{ref}}\}. \quad (1)$$

Let $\tau_t = \alpha_{\text{sel}}/m_t$ when Bonferroni is enabled and $\tau_t = \alpha_{\text{sel}}$ otherwise. If $p_t^{\star, \text{ref}} \geq \tau_t$, Stage A returns no feature and the node becomes terminal. If $p_t^{\star, \text{ref}} < \tau_t$, the selected feature $j_t^{\star, \text{ref}}$ is drawn uniformly from $M_t^{\star}$ using reservoir sampling, and the node enters Stage B.

During adaptive tree growing, Stage A uses the same decision structure but can order features by a preliminary score and evaluate only the subset E_t . The returned value q_t^{feat} is used to grow the tree; it is not an exhaustive fixed- B p -value covered by Theorem 1. Under the exhaustive reference rule with Bonferroni correction, $\min(1, m_t p_t^{\star, \text{ref}})$ is a conservative complete-null p -value for the fixed-node Stage A test. When feature muting is enabled, features with non-rejecting Stage A p -values can be removed from descendant feature pools. When muting is disabled, descendants keep $F_{t, \text{avail}}$ except for deterministic constant feature pruning.

Stage B (threshold search). Given a selected feature $j_t^{\star}$, Stage B starts from midpoints between ordered unique values of $X_{t,j_t^{\star}}$. The exact method uses all such midpoints. The random method samples a bounded subset of midpoints, while the percentile and histogram methods choose bounded representative thresholds derived from the midpoint distribution. Thresholds that would leave either child below the minimum leaf size are filtered out. If no threshold remains, Stage B returns no split.

For the remaining finite threshold set $C_{t,j_t^{\star}}$, Stage B selects the threshold used by the tree. The tested statistic at threshold c is the weighted child impurity

$$\frac{|Y_t^L(c)|}{|Y_t|} \text{Imp}(Y_t^L(c)) + \frac{|Y_t^R(c)|}{|Y_t|} \text{Imp}(Y_t^R(c)),$$

where Imp is the chosen node impurity measure. This statistic is used in a left-tail test, and the exhaustive fixed- B rule chooses the threshold with the smallest Stage B p -value, with uniform tie breaking. During adaptive tree growing, threshold scanning may reorder thresholds and stop after the first rejecting threshold, so the returned Stage B score is a tree-construction score rather than a global minimum over all retained thresholds. Let $\tau_t^{\text{split}} = \alpha_{\text{split}}/|C_{t,j_t^{\star}}|$ when Bonferroni is enabled for Stage B and $\tau_t^{\text{split}} = \alpha_{\text{split}}$ otherwise. If no evaluated Stage B p -value is below τ_t^{split} , the node becomes terminal. After a threshold passes the Stage B test, the final minimum required-improvement check uses the corresponding weighted impurity decrease. Stage B chooses the split used by the tree; the returned Stage B score is not a valid post-selection p -value. The training skeleton in Algorithm 1 summarizes this flow and, for the benchmarked CIT and CIF configurations, stores two values at each split: the Stage A permutation p -value for the selected feature and the Stage B permutation p -value for the selected threshold.

Joint Stage B test (max-type). The per-threshold rule above tests each candidate $c \in C_{t,j_t^*}$ separately at level α_{split}/K with $K = |C_{t,j_t^*}|$, and the permutation budget must scale with K so that the adjusted level can be resolved, which costs on the order of $K^2/\alpha_{\text{split}}$ impurity evaluations per node. The implementation also provides a joint construction. Write $S_{b,c}$ for the weighted child impurity at candidate c under the observed response ($b = 0$) and under permutation $b = 1, \dots, B$. Each column is standardized by the mean μ_c and standard deviation σ_c of its $B+1$ entries, candidates with $\sigma_c = 0$ or an empty child are dropped, and the row statistic is

$$T_b := \min_c \frac{S_{b,c} - \mu_c}{\sigma_c}, \quad p_t^{\max} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \leq T_0\}}{B+1}, \quad (2)$$

with the split placed at $\arg \min_c (S_{0,c} - \mu_c)/\sigma_c$. Stage B rejects when $p_t^{\max} < \alpha_{\text{split}}$, without division by K . This is a single-step max-T statistic in the sense of Westfall and Young [43], applied to a minimum because smaller impurity is more extreme, with the empirical null standardization of Pollard and van der Laan [32]; it has the same standardize-then-optimize form as the conditional inference split statistic of Hothorn et al. [18], with Monte Carlo column moments replacing the exact conditional moments of Strasser and Weber [36] because impurity is not a linear statistic. Standardization is what makes the minimum meaningful: candidates near the tails of X_{t,j_t^*} isolate few observations and have wide null distributions, and the unstandardized minimum is drawn to them on heavy-tailed responses. Validity needs only about $1/\alpha_{\text{split}}$ permutations; the implementation uses $B = 999$ under the named budget rules, so the cost is on the order of BK evaluations against $K^2/\alpha_{\text{split}}$ for the per-threshold rule. When every candidate is excluded the test returns $p_t^{\max} = 1$ and no split. Corollary 2 gives the fixed-node guarantee and Section 5.3 the measured calibration, cost, and behavior. The max-type rule was added after the benchmark had been run, when the cost of the per-threshold rule was traced to its K -scaled budget, so the benchmark configurations in this paper use the per-threshold rule, which remains the default in this version.

2.2 Monte Carlo permutation p -values

Let T_{obs} be the observed statistic and $T_1, \dots, T_B$ the same statistic computed on B random label permutations. For a right tail test we use the Phipson–Smyth +1 p -value [29, 31], where $\mathbf{1}\{\cdot\}$ denotes the indicator function:

$$p_{\text{MC}}^{\geq} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_{\text{obs}}\}}{B+1}. \quad (3)$$

For a left tail test we analogously define

$$p_{\text{MC}}^{\leq} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \leq T_{\text{obs}}\}}{B+1}. \quad (4)$$

Stage A uses the right tail convention and Stage B the left tail convention; ties count as exceedances in both cases.

Algorithm 1 Conditional inference tree training skeleton (Stage A $\rightarrow$ Stage B)

Require: Training data (X, Y) , hyperparameters θ

Ensure: Trained tree $\mathcal{T}$

```
1:  $p \leftarrow$  number of columns of  $X$ 
2: return GROWNODE( $X, Y, 1, \{1, \dots, p\}, \theta$ )
3: function GROWNODE( $X_t, Y_t, d, F_{\text{avail}}, \theta$ )
4:   if STOP( $X_t, Y_t, d, \theta$ ) then
5:     return LEAF( $Y_t$ )
6:   end if
7:    $(j_t^*, q_t^{\text{feat}}, m_t, F'_{\text{avail}}) \leftarrow$  STAGEA( $X_t, Y_t, F_{\text{avail}}, \theta$ )
8:   if  $j_t^* = \perp$  then
9:     return LEAF( $Y_t$ )
10:  end if
11:   $(c_t^*, q_t^{\text{split}}) \leftarrow$  STAGEB( $X_t, Y_t, j_t^*, \theta$ )
12:  if  $c_t^* = \perp$  then
13:    return LEAF( $Y_t$ )
14:  end if
15:   $(X_t^L, Y_t^L, X_t^R, Y_t^R) \leftarrow$  PARTITION( $X_t, Y_t, j_t^*, c_t^*$ )
16:   $\Delta_t \leftarrow$  IMPURITYDECREASE( $Y_t, Y_t^L, Y_t^R, \theta$ )
17:  if  $\Delta_t$  is below the minimum required impurity decrease then
18:    return LEAF( $Y_t$ )
19:  end if
20:  Add  $\Delta_t$  to the feature-importance accumulator for  $j_t^*$ 
21:   $u \leftarrow$  internal node with split  $(j_t^*, c_t^*)$  and stored p-value fields  $(q_t^{\text{feat}}, q_t^{\text{split}})$ 
22:   $u.\text{left} \leftarrow$  GROWNODE( $X_t^L, Y_t^L, d + 1, F'_{\text{avail}}, \theta$ )
23:   $u.\text{right} \leftarrow$  GROWNODE( $X_t^R, Y_t^R, d + 1, F'_{\text{avail}}, \theta$ )
24:  return  $u$ 
25: end function
```

2.3 Forests and runtime hyperparameters

CIF combines bootstrap trees and averages their predictions. For feature selection, it sums each fitted tree’s normalized split importances and renormalizes the forest vector. Each CIF tree uses the same Stage A and Stage B node rules as CIT [3, 16]. The fixed-node theorem applies only to the Stage A reference test described above. Across the CIT/CIF benchmark configurations, we hold Bonferroni correction, adaptive stopping, feature muting, feature scanning, threshold scanning, histogram-256 thresholding, and CIF bootstrap sampling fixed. The varying settings are selector choice and honesty.

Runtime depends on the realized work at each node: features tested in Stage A, thresholds generated and retained in Stage B, permutations evaluated before stopping, and features carried into the node. Adaptive stopping changes the number of permutations evaluated for each test [2, 9]. Histogram thresholding reduces the Stage B threshold set by replacing exhaustive cutpoints with binned thresholds. Feature and threshold scanning change the order in which features or thresholds are tested under early stopping; feature muting can reduce the feature pool inherited by descendants. Appendix D gives algorithm and reproducibility details, Appendix E gives runtime and memory accounting, and Section 5.2 reports the measured timing effects.

2.4 Feature rankings

The experiments evaluate each method through the ranking it produces on the training fold. CIT and CIF rankings are fitted split-importance rankings, not rankings of Stage A p -values. For a fitted CIT, feature j receives the sum, over internal nodes that split on j , of the impurity decrease at that node: parent impurity minus the weighted child impurity. If the total importance is positive, the vector is normalized to sum to one; if the tree contributes no positive impurity decrease, the vector remains zero. CIF sums these tree importance vectors over trees and then normalizes the forest vector in the same way. Stage A determines which features enter threshold optimization, while impurity decrease scores only the accepted splits by their local reduction in impurity. Larger importances are ranked earlier, and features never used by a split receive zero importance.

This split-importance ranking differs from standard random-forest impurity importance in how a feature enters threshold search. In CART-style trees, the feature and threshold are chosen together by an impurity search, so a feature with more possible thresholds has more chances to produce a large apparent impurity decrease [38]. In CIT and CIF, Stage A first selects a feature by a permutation test; Stage B then searches thresholds only for that feature. This reduces the advantage that high-cardinality features get from having more possible thresholds. We use these fitted split-importance scores as rankings and evaluate them through downstream top- k prediction and synthetic feature recovery.

3 Fixed-node Stage A control

This section analyzes the exhaustive fixed- B Stage A feature selection rule at a fixed node. The theorem proves superuniformity for a single +1 Monte Carlo permutation p -value, and the corollary applies Bonferroni correction across the fixed-node Stage A tests. In the notation of Section 2.1, this is the reference case where every feature in F_t is tested with the same fixed nodewise budget B . All probabilities below condition on (X_t, U) , where U collects label-independent auxiliary randomness other than the Monte Carlo permutation draws.

Theorem 1 (+1 permutation p -values are superuniform). *Assume A0.1 through A0.5 from Appendix A.2. Under the nodewise complete permutation null at the fixed node t , conditional on (X_t, U) , the observed statistic together with the B random-permutation statistics has the rank distribution of an exchangeable tuple of length $B + 1$. Define the right-tail +1 Monte Carlo p -value*

$$p_{\text{MC}}^{\geq} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_{\text{obs}}\}}{B + 1}. \quad (5)$$

Then for every $\alpha \in [0, 1]$,

$$\mathbb{P}(p_{\text{MC}}^{\geq} \leq \alpha \mid X_t, U) \leq \alpha. \quad (6)$$

This is the standard exchangeable-rank result for Monte Carlo permutation tests [8, 14, 29]. Appendices B and C state the exchangeability condition and give the proof. The left-tail version follows by applying the same result to $-T$.

Corollary 1 (Stage A complete null control at a fixed node). *Assume A0.1 through A0.5 from Appendix A.2. Under the nodewise complete null at t , let F_t be nonempty and write $m_t = |F_t| \geq 1$. Let Stage A reject when*

$$\min_{j \in F_t} p_{t,j} \leq \alpha_{\text{sel}}/m_t. \quad (7)$$

The tree-growing rule uses a strict comparison, so its rejection event is a subset of the nonstrict event above. Then

$$\mathbb{P}(\exists j \in F_t : p_{t,j} \leq \alpha_{\text{sel}}/m_t \mid X_t, U) \leq \alpha_{\text{sel}}. \quad (8)$$

Combining Theorem 1 with the Bonferroni union bound over the m_t Stage A tests gives fixed-node Stage A control under the complete null. The result is local: it does not cover partial-null familywise error control, p -values for selected features, or error control for fitted trees and forests.

Corollary 2 (Stage B max-type control at a fixed node). *Assume A0.1 through A0.5 from Appendix A.2 at a fixed node t , with the tested feature and the finite candidate set C fixed as functions of (X_t, U) alone, a fixed budget B with no optional stopping, and left-tail ties counted with $\leq$. Let $p_t^{\max}$ be the max-type Stage B p -value of Equation (2) with column moments computed over all $B + 1$ rows. Under the nodewise complete permutation null, conditional on (X_t, U) , $\mathbb{P}(p_t^{\max} \leq \alpha \mid X_t, U) \leq \alpha$ for every $\alpha \in [0, 1]$.*

The argument reduces to Theorem 1 in four steps. Under the complete null the $B + 1$ rows of the impurity matrix $(S_{b,c})$ are exchangeable: row 0 is the observed labels and rows $1, \dots, B$ are independent uniform permutations of them with the identity adjoined [14], and Lemma 2 applies verbatim to the vector-valued statistic $c \mapsto S_{b,c}$ in $\mathbb{R}^K$, since nothing in its proof uses that the statistic is scalar. Column standardization uses the mean and standard deviation of all $B + 1$ entries of each column, which are symmetric functions of the rows, so the standardized matrix has exchangeable rows as well; the exclusion of candidates with an empty child or zero column variance is likewise a function of the whole column. The row minimum is one fixed function applied to every row, so $T_0, \dots, T_B$ are exchangeable. The inclusive-rank p -value of an exchangeable tuple is superuniform by the proof of Theorem 1, applied to $-T$ for the left tail. The moments must include row 0: estimating them from the permuted rows alone singles out the observed row, breaks the symmetry the argument uses, and can be anti-conservative. The guarantee is weak familywise control over the K candidates, the probability of declaring any split under the node’s global null. It is a fixed-node, fixed- B statement for a feature fixed without reference to Y_t ; it does not cover the adaptive variant, whose column moments and chosen threshold move with the stopping time, and it is not a post-selection p -value for a feature chosen by Stage A from the same responses.

4 Experimental design

The experiments ask whether rankings produced by CIT and CIF place predictive features early enough for fixed downstream learners. For each training fold, a method produces a feature ranking, and fixed downstream learners evaluate the selected features on the held-out fold. We then summarize overall ranks, how often CIF performs well across datasets, high-dimensional behavior, recovery on synthetic data with known informative features, CIF ranking ablations, and feature sampling in forests.

4.1 Benchmark setup

The benchmark uses 5 random seeds, with 5-fold cross-validation within each seed. Classification fits logistic regression (LR), support vector machine (SVM), and k-nearest neighbors (KNN) as downstream models and reports balanced accuracy, defined as mean recall across classes. Regression fits ridge regression, support vector regression (SVR), and KNN and reports R^2 . The main tables use the standard values $k \in \{5, 10, 25, 50, 100\}$. Downstream learner settings are fixed. Logistic regression uses balanced class weights and a 1,000-iteration limit; SVM uses an RBF kernel with

unit regularization, $\gamma = \text{scale}$, and balanced class weights; KNN uses 5 distance-weighted neighbors; ridge uses unit penalty strength; and SVR uses an RBF kernel with unit regularization, $\epsilon = 0.1$, and $\gamma = \text{scale}$.

For each seed and fold, feature-standardization parameters are estimated on the training fold and then applied to the held-out fold. The ranking method uses only the standardized training fold and produces the ordered feature list described in Section 2.4. For each k , we take the top- k features from that ranking, refit standardization on the selected training columns, apply the same transform to the selected held-out columns, fit the downstream model on the selected training data, and evaluate it on the held-out fold.

The downstream evaluation also records performance using the full feature set, $k = p$, for every dataset. For datasets with more than 100 features, the separate high- p analysis adds fixed values $k \in \{150, 200, 300, 500, 750, 1,000\}$ and fractional values $\lceil 0.25p \rceil$, $\lceil 0.5p \rceil$, $\lceil 0.75p \rceil$, keeping only values no larger than p . The main tables average only the standard k values.

4.2 Benchmark comparisons

The benchmark averages scores in three steps. First, for each (dataset, downstream model, k) combination, scores are averaged over folds and seeds. Second, each dataset score averages those fold-and-seed means over downstream models and over the standard k values available for the methods in that comparison. Third, the tables average dataset scores over datasets.

The real-data classification benchmark contains 23 datasets. On **gisette** and **isolet**, some method runs were excluded for operational reasons (Appendix D lists them), so the all-method rank summary uses the 21 datasets with results for every method, and each pairwise comparison uses the datasets where both methods are present. The complete-case classification analysis, used for bootstrap intervals and omnibus rank testing, contains 13 datasets with all 17 methods, all three downstream learners, and all five standard values of k . Regression contains 8 datasets; the analogous rank summary uses the 6 complete-case datasets with all methods, downstream learners, and standard k values available.

By- k results are reported separately for $k = 5, 10, 25, 50, 100$. The corresponding classification dataset counts are 21, 20, 14, 14, 13; the regression counts are 8, 8, 7, 7, 6. Pairwise CIF comparisons stratified by k use the dataset counts reported with the corresponding rows. The 13-dataset classification and 6-dataset regression summaries are complete-case analyses, retaining only datasets with every method, downstream learner, and standard k value.

4.3 Datasets

The real-data benchmark includes 23 classification datasets and 8 regression datasets. The separate high- p analysis restricts attention to the 15 classification datasets and 6 regression datasets with more than 100 features. The full inventories of the real and synthetic datasets are listed in Appendix F, which also summarizes the synthetic designs and their parameter choices.

Feature recovery uses 8 synthetic classification datasets and 8 synthetic regression datasets with known informative features and controlled noise structure. A separate study of feature sampling uses $n = 250$ and varies $p \in \{100, 500, 1,000\}$ and $n_{\text{informative}} \in \{1, 2, 5, 10\}$. That study compares CIT, a CART decision tree (DT), a random threshold tree (RT), CIF, CIF-all, random forests (RF), and ExtraTrees (ET), using 1,000 trees for forest methods. CIF-all denotes the CIF variant that evaluates all nonconstant features at each split.

4.4 Compared methods

The benchmark includes three types of feature selectors: permutation-test filters, embedded tree or ensemble methods, and wrapper baselines. Permutation-test filters compute univariate dependence statistics and rank features by their permutation p -values: multiple correlation (MC) and randomized dependence coefficient (RDC) for classification, and Pearson correlation (PC), distance correlation (DC), and RDC for regression. The RDC filter keeps the empirical-CDF random feature map from Lopez-Paz et al. [28] but replaces the canonical-correlation solve with the maximum absolute pairwise correlation across projected columns. It uses 10 random projections (20 sine and cosine columns). In a 5-seed, 5-fold sensitivity analysis on four small classification datasets, using 20 instead of 10 projections required more than three times the median selector time, changed mean balanced accuracy by at most 0.0052, and retained at least 95.4% mean overlap between selected feature sets. Distance correlation follows Székely et al. [40].

Embedded methods rank features using tree or ensemble importance scores. These methods are CART decision trees (DT), randomized trees (RT), CIT, CIF, random forests (RF) [3], ExtraTrees [11], XGBoost [5], LightGBM [21], CatBoost [33], and the partykit reference implementations ctree and cforest [15, 18, 19]. Wrapper baselines score features through auxiliary random-forest fits: Boruta [24], permutation importance (PI) [3, 38], conditional permutation importance (CPI) [6], and random-forest recursive feature elimination (RF-RFE) [12, 30].

In this benchmark, CPI uses stratified conditional permutation with correlation-based strata. For each target feature, it trains a 100-tree random forest on a training split and scores a 20% validation split. It then identifies validation-set features with absolute correlation at least 0.5 with the target feature, forms five-bin percentile strata from those conditioning features, and permutes the target feature within strata. If no conditioning feature meets the correlation threshold, the target feature is permuted globally.

Ranking rules use each method’s natural score direction. Embedded tree and ensemble baselines rank features by decreasing fitted importance: DT, RT, RF, ExtraTrees, XGBoost, LightGBM, and CatBoost. Permutation-test filters rank by increasing p -value, with dependence score as the secondary key. The ctree reference ranks features by split-use counts. For cforest, we use partykit’s unconditional variable-importance scores with one permutation; CIF uses split-importance rankings from accepted conditional-inference splits. The cforest results therefore refer to this benchmarked partykit importance setting. Boruta and recursive feature elimination rank by their fitted rank variables, with smaller ranks first. PI and CPI rank by decreasing importance; the CPI row uses the stratified conditional-permutation procedure described above. Ties are broken by deterministic, method-specific order for reproducibility.

4.5 Configuration selection

Several methods, including CIT, CIF, XGBoost, LightGBM, ctree, and cforest, were evaluated under multiple configurations. Permutation-test filters used one configuration per statistic. For each task, the paper reports one configuration per method, selected by mean score over real datasets, downstream models, and the standard values $k \in \{5, 10, 25, 50, 100\}$. Methods with only one configuration are treated as fixed. The selected configuration is then held fixed across datasets for that task. Because configuration selection and reporting use the same real-data benchmark, the reported scores, intervals, and rank summaries are descriptive. As a sensitivity check, we repeat configuration selection in leave-one-dataset-out (LODO) form for both tasks. In classification, each of the 13 complete-case datasets is evaluated using configurations chosen from the other 12 datasets. In regression, each of the 6 complete-case datasets is evaluated using configurations chosen from

the other 5 datasets. The downstream models, k values, and averaging within each dataset are unchanged.

For the synthetic analysis, configurations are selected separately from the real-data benchmark. Each method is assigned the configuration with the highest average recovery of the true informative features over $k = 5, 10, 25, 50$, and 100. The benchmarked CIT and CIF configurations use adaptive sequential stopping, Bonferroni correction, feature muting, feature scanning, threshold scanning, and 256-bin histogram thresholding. The benchmarked CIT and CIF variants differ in selector and honesty; CIF is run as a bootstrap forest. Each CIF runtime ablation changes one setting.

To isolate which parts of the CIF ranking matter, we run a ranking ablation on the real-data benchmark datasets (22 classification and 8 regression). The ablation holds the selected CIF configuration fixed and changes one component at a time: replacing fitted split importance with split counts, disabling feature muting, disabling bootstrap sampling, or reducing the forest to one tree. Each variant is evaluated with the same downstream learners, folds, seeds, and standard top- k values as the main benchmark, and every comparison is paired with the reference configuration within seed and fold.

4.6 Stage B construction comparison

A separate study compares the per-threshold Bonferroni rule and the max-type rule of Equation (2) under the multiple correlation and Pearson correlation selectors with adaptive and exhaustive stopping; its three parts were fixed in advance. Candidate thresholds come from the histogram method at settings of 16, 64, and 256 bins, which yields one more candidate than the setting, capped at the number of distinct values in the node, so the 256-bin setting yields 100 and 200 candidates at $n = 100$ and $n = 200$. The first part estimates the false-split rate of a depth-one tree under the global null with five independent Gaussian predictors and an independent response, at $n \in \{100, 200, 500\}$ and the three bin settings, with 2,000 replicates per cell; the rate measures the complete node decision, the Stage A gate over five predictors followed by the Stage B test, and is therefore below the Stage B level alone. The second times one tree on ten Gaussian predictors with a planted linear signal in three of them at $n \in \{1,000, 4,000, 16,000\}$ and the same bin settings, as the median of three fits with a 900-second cap. The third fits one tree on six benchmark datasets fixed by size, three classification (vowel, spam, page-blocks) and three regression (imports-85, residential, facebook), at the 256-bin setting with five-fold cross-validation, recording held-out score, tree depth, fitting time, and the Spearman agreement of the two rules’ feature importances within each fold. All fits ran on one 32-core cloud instance of the class used for the runtime ablations; a fit exceeding the cap is reported as censored. A companion head-to-head timing on the recommended forest configuration adds the max-type rule to eight of the ten real datasets with at least 500 observations (isolet and gisette were not run) and to the synthetic scaling grid at $n \in \{500, 2,000, 8,000\}$ and $p \in \{20, 100, 500\}$, refitting the per-threshold configuration in the same run.

5 Results

5.1 Real-data benchmark

Table 1 reports the main real-data comparison. Classification uses the 21 datasets with results for every method; the full classification collection has 23 datasets, and **gisette** and **isolet** enter only the comparisons whose methods completed there (Appendix D lists the excluded runs). Regression uses all 8 datasets. Within each dataset, scores are first averaged over downstream learners and the

standard k values shared by the compared methods, then converted to ranks. Lower mean rank is better.

Classification		Regression	
Method	Mean rank	Method	Mean rank
RF-RFE	4.19	ExtraTrees	5.00
XGBoost	5.81	CIF	6.25
CIF	5.86	CatBoost	6.75
RF	5.86	RF-RFE	6.88
LightGBM	6.05	RF	7.63
Boruta	6.62	RT	8.25
CatBoost	6.76	cforest	8.75
ExtraTrees	7.33	DT	9.38
cforest	8.33	Boruta	9.50
DT	8.62	PC filter	9.88
RDC filter	11.05	LightGBM	10.13
PI	11.67	XGBoost	10.13
MC filter	11.86	RDC filter	11.00
RT	12.81	CIT	11.13
ctree	12.86	ctree	11.38
CIT	13.14	PI	11.75
CPI	14.19	DC filter	12.25
		CPI	15.00

Table 1: Main real-data comparison. Ranks are computed within each dataset after scores are averaged over downstream learners and the standard k values shared by the compared methods, then averaged across datasets. Classification uses the 21 datasets with results for every method; regression uses all 8 datasets.

With selected configurations fixed, CIF ties RF for 3rd of 17 classification methods and ranks 2nd of 18 regression methods. Table 2 compares CIF directly with ctree, cforest, and CIT. Appendix G gives the learner-by- k tables (Tables 20 and 21), pairwise CIF-comparison heatmaps (Figures 6 and 7), and seed-sensitivity tables (Tables 22 and 23); each analysis reports its dataset count.

Task	Compared with	Datasets	Mean diff.	W-L
Classification	ctree	21	0.037	19-2
Classification	cfoster	22	0.010	17-5
Classification	CIT	23	0.032	22-1
Regression	ctree	8	0.157	6-2
Regression	cfoster	8	0.021	6-2
Regression	CIT	8	0.234	7-1

Table 2: Direct CIF comparisons against ctree, cforest, and CIT. Mean differences are CIF minus the compared method after averaging within each dataset over supported downstream learners and standard values of k ; classification uses balanced accuracy and regression uses R^2 . W-L reports wins and losses over datasets where both methods were run.

Table 2 shows CIF ahead on average in all six direct pairings. On the complete-case datasets, CIF is also ahead of ctree, cforest, and CIT in both tasks. The 95% bootstrap CIs for mean CIF-minus-comparator differences are as follows. Classification (13 datasets): ctree [+0.026, +0.073], cforest [+0.002, +0.024], CIT [+0.027, +0.062]. Regression (6 datasets): ctree [+0.029, +0.421], cforest [-0.032, +0.090], CIT [-0.002, +0.766]. The regression intervals for CIF versus cforest and versus CIT cross zero; the classification intervals and the regression ctree interval are positive. The regression intervals are wider because fewer datasets are available and some comparator mean R^2 values are negative.

CIF ablations. Table 3 compares the selected CIF configuration with four targeted changes on the real-data benchmark datasets: split-count ranking, disabling bootstrap sampling, disabling feature muting, and using one tree. Each changed variant is paired with the reference in the same

seed and fold. Reducing CIF to one tree is the only change with a material effect: it lowers the score on every dataset in both tasks, by 0.071 balanced accuracy on average in classification. Split-count ranking, disabling bootstrap sampling, and disabling feature muting change classification balanced accuracy by at most 0.001 on average, with intervals that include zero. The regression means for these three changes are pulled down by the three small `coepra` datasets, where R^2 is unstable across folds; their medians are within 0.007 of zero and their win-loss counts are near even.

Task	CIF change	Mean diff.	Median diff.	95% CI	W-L
Classification	Split-count ranking	-0.001	0.000	[-0.005, +0.002]	12-9
Classification	Disable bootstrap	-0.001	0.000	[-0.004, +0.003]	9-12
Classification	Disable feature muting	0.001	0.000	[-0.001, +0.002]	13-5
Classification	Use one tree	-0.071	-0.043	[-0.101, -0.045]	0-22
Regression	Split-count ranking	-0.053	-0.003	[-0.142, -0.002]	2-6
Regression	Disable bootstrap	-0.064	-0.007	[-0.128, -0.010]	4-4
Regression	Disable feature muting	-0.157	0.000	[-0.468, +0.001]	4-4
Regression	Use one tree	-0.658	-0.059	[-1.692, -0.054]	0-8

Table 3: CIF ablations on the real-data benchmark. Differences compare each changed variant with the selected CIF configuration using split-importance ranking, paired within seed and fold. Scores are averaged within each dataset over downstream learners, supported standard values of k , and the 25 paired fold $\times$ seed replicates. Classification uses balanced accuracy; regression uses R^2 . The confidence intervals are percentile bootstrap intervals for the mean over dataset-level differences from 20,000 replicates. Positive values favor the changed CIF variant. W-L counts datasets where the changed variant is higher or lower than the reference; exact ties are omitted. The classification rows use 22 datasets and the regression rows use 8 datasets.

The complete-case Friedman tests use dataset-level method means. Classification: $\chi^2(16) = 140.46$, $p < 0.001$, Kendall’s $W = 0.68$. Regression: $\chi^2(17) = 26.15$, $p = 0.072$, Kendall’s $W = 0.26$, which does not reach the 0.05 level, so the regression rank ordering is reported as a descriptive summary of the 6-dataset panel rather than as evidence of method differences. These intervals and rank summaries describe the benchmark-selected configurations. The LODO analysis below checks whether those configurations are stable under one-dataset holdout.

In the 13-dataset classification panel, LODO ranks CIF eighth of 17 on average (mean rank 6.85), and CIF reselects the main-benchmark configuration in 11 of 13 holdouts, using 2 distinct configurations. In the 6-dataset regression panel, LODO ranks CIF sixth of 18 on average (mean rank 7.33), behind ExtraTrees, CatBoost, RF-RFE, RF, and RT; CIF reselects the global regression configuration in 4 of 6 holdouts. Tables 18 and 19 give the confidence intervals and LODO details.

Table 4 reports how often CIF appears in the top half or top 3 and how often it beats tree baselines.

Summary	Classification	Regression
Main rank	3.5/17	2/18
Top half	17/21	5/8
Top 3	4/21	2/8
Win vs ctrees	19/21	6/8
Win vs cforest	17/22	6/8
Win vs CIT	22/23	7/8
Win vs DT	16/23	5/8
Win vs RT	21/23	5/8

Table 4: Dataset breadth for the selected CIF configuration. Top half and Top 3 counts use the datasets from Table 1. Direct win rows use datasets where both methods were run. The fractional classification main rank reflects a tie with RF.

In classification, CIF is in the top half on 17 of the 21 all-method datasets, and in the top 3 on 4 of 21. In regression, CIF is in the top half on 5 of 8 datasets and in the top 3 on 2 of 8. Against the greedy single-tree baselines, CIF beats DT on 16/23 classification datasets and 5/8 regression datasets, and beats RT on 21/23 classification datasets. The RT regression comparison is close: CIF is ahead on 5/8 datasets, with a mean difference near zero.

Figures 1 and 2 report mean rank separately by k . In classification, CIF’s mean rank is 6.9 at $k = 5$, 8.2 at $k = 10$, 6.2 at $k = 50$, and 5.6 at $k = 100$. In regression, CIF’s mean rank is 8.2 at $k = 5$, 7.1 at $k = 25$, and 8.3 at $k = 100$. These by- k results add context to Table 1: CIF is strongest at larger displayed k values in classification and at $k = 25$ in regression. The aggregate ctree comparison uses 21 classification datasets and the cforest comparison uses 22. For $k = 5, 10, 25, 50, 100$, the classification columns use 21, 20, 14, 14, and 13 datasets, respectively; the regression columns use 8, 8, 7, 7, and 6 datasets, respectively. Complete-case analyses use 13 classification datasets and 6 regression datasets.




Figure 1: Classification mean rank by number of selected features. Rows show all 17 feature selection methods in the classification benchmark, averaged across downstream models at each value of k . Lower ranks are better. The columns for $k = 5, 10, 25, 50, 100$ use 21, 20, 14, 14, and 13 datasets, respectively.




Figure 2: Regression mean rank by number of selected features. Rows show all 18 feature selection methods in the regression benchmark, averaged across downstream models at each value of k . Lower ranks are better. The columns for $k = 5, 10, 25, 50, 100$ use 8, 8, 7, 7, and 6 datasets, respectively.

5.2 Runtime ablations

The runtime ablations identify which benchmark settings have the largest effect on fitting time and report how much the ranking scores move when those settings change. Each row changes one setting and reports elapsed wall-clock fit time relative to the selected configuration for the same estimator. Ratios above 1 are slower than that reference, and ratios below 1 are faster. CIT and CIF are shown separately because the CIT run records fit time and synthetic top-10 feature recovery, while the CIF runs also record downstream score changes. The main benchmark remains the primary performance comparison. Appendix E links each ablation to the affected work terms.

CIT change	Runtime ratio	Largest top-10 F1 change
Disable adaptive stopping	3.2–8.3×	≤ 0.40
Exact threshold search	0.82–1.10×	≤ 0.06
Disable feature scanning	0.57–3.16×	≤ 0.38

Table 5: CIT runtime ablations. Runtime ratios are paired by seed and dataset against the selected CIT configuration and summarized across the real and synthetic classification and regression runs. Top-10 F1 changes are absolute changes on synthetic datasets with known informative features, where top-10 F1 is the harmonic mean of precision and recall for recovering informative features among the first 10 ranked features. Numbers are rounded for display. The final column is the largest absolute top-10 F1 change across the synthetic task groups. The dataset-type counts are 7 real classification, 8 synthetic classification, 2 real regression, and 6 synthetic regression.

CIT runtime ablations. Table 5 shows that adaptive stopping is the setting that matters for a single tree. Disabling it makes fits 3.2–8.3× slower by median dataset-level ratios in all four task groups. It also changes the fitted tree: without early stopping the mean depth on the synthetic datasets rises from 5.8 to 9.0 (4.8 to 7.7 in classification, 7.1 to 10.6 in regression), and top-10 feature recovery moves by up to 0.40, with the largest changes on the Toeplitz and confounder designs and none on the weak-signal designs. A single tree exposes every difference in the realized sequence of features, thresholds, and nodes, which the forest averages away. Exact threshold search and feature scanning change runtime by less than a factor of 3.2 in either direction and recovery by at most 0.06 and 0.38.

CIF change	Runtime ratio	Downstream score change	Synthetic feature recovery change
Disable adaptive stopping	6.1–6.5× synthetic; 483–717× real	≤ 0.010	≤ 0.007
Exact threshold search	1.1–21×	≤ 0.010	≤ 0.010
Disable feature scanning	1.2–4.2×	≤ 0.006	≤ 0.003

Table 6: CIF runtime ablations with score changes. Runtime ratios are relative to the selected CIF configuration. Adaptive stopping and feature scanning use median dataset-level ratios. The exact-threshold row compares group mean elapsed time with the histogram-256 reference. The score columns give the largest absolute downstream score change and synthetic feature-recovery change across the task groups used for each row. Inequality entries are rounded upward to the nearest 0.001. The task-group coverage matches Table 5.

CIF runtime ablations. Table 6 shows that adaptive stopping is also the dominant control for forests, and that its value depends on the data. On the synthetic datasets, disabling it makes fits 6.1–6.5× slower by median dataset-level ratios. On the real datasets the same change makes fits 483–717× slower: with hundreds of predictors and a Bonferroni-adjusted level, a null predictor needs thousands of permutations to be rejected without early stopping, and adaptive stopping dismisses it after a few dozen. Exact threshold search is 1.1–21× slower than histogram-256 by group mean elapsed times, with the largest ratio on the real regression datasets, and disabling feature scanning costs 1.2–4.2×. Downstream score changes are at most 0.010 and synthetic feature-recovery changes at most 0.010 across all three rows. Removing Bonferroni correction is faster for both CIT and CIF, but it changes the statistical rule and yields trees with more selected features; the selected setting keeps Bonferroni correction.

5.3 Stage B construction comparison

The complete-node false-split rate is below 0.05 for both Stage B constructions in all 36 design cells, 72 measurements (Table 7); the constructions differ in how far below. Under the per-threshold Bonferroni rule the rate falls as the bin setting grows, from 0.0145 at 16 bins to 0.0040 at 256 in classification with $n = 500$ and exhaustive stopping, because adjacent thresholds induce nearly identical splits and the union bound charges for each. Under the max-type rule it stays between 0.025 and 0.038 in every cell and rises slightly with the bin setting, with cell means of 0.030, 0.032, and 0.032.

Task	n	Bins	Bonferroni		Max-type	
			Adaptive	Exhaustive	Adaptive	Exhaustive
Classification	100	16	0.0180	0.0185	0.0320	0.0350
	100	64	0.0130	0.0135	0.0355	0.0370
	100	256	0.0095	0.0075	0.0355	0.0375
	200	16	0.0150	0.0165	0.0280	0.0295
	200	64	0.0095	0.0100	0.0300	0.0300
	200	256	0.0070	0.0075	0.0300	0.0310
	500	16	0.0130	0.0145	0.0250	0.0255
	500	64	0.0105	0.0090	0.0275	0.0280
	500	256	0.0045	0.0040	0.0280	0.0295
Regression	100	16	0.0240	0.0285	0.0310	0.0340
	100	64	0.0195	0.0195	0.0345	0.0360
	100	256	0.0155	0.0160	0.0335	0.0370
	200	16	0.0285	0.0250	0.0285	0.0310
	200	64	0.0240	0.0235	0.0320	0.0335
	200	256	0.0110	0.0115	0.0305	0.0345
	500	16	0.0240	0.0250	0.0290	0.0295
	500	64	0.0195	0.0180	0.0265	0.0290
	500	256	0.0125	0.0120	0.0270	0.0295

Table 7: False-split rate of a depth-one tree under the global null at level 0.05, by Stage B construction and stopping mode, over 2,000 replicates per cell with five independent Gaussian predictors and an independent response. Bins is the histogram threshold setting; the realized candidate count is one more than the setting, capped at the number of distinct values. Every 95% Wald confidence interval lies below 0.05; the widest half-width is below 0.009.

The cost difference is where the constructions separate (Table 8). With exhaustive stopping, one tree at the 256-bin setting takes 60 seconds at $n = 1,000$ and 426 to 486 seconds at $n = 4,000$ under the Bonferroni rule and exceeds the 900-second cap at $n = 16,000$; the max-type rule takes 0.5, 1.5 to 1.6, and 6.2 to 6.7 seconds at the same settings. The exhaustive ratio grows with the bin setting, from 2.0–6.4 at 16 bins to 14–49 at 64 and 119–318 at 256, faster than the linear growth in K that the K^2/α against BK accounting alone predicts. With adaptive stopping the Bonferroni rule dismisses most candidates after a few dozen permutations and the ratio is 1.6–4.7 at 16 bins, 3.2–16 at 64, and 5.9–84 at 256. The rules also grow different trees on these data: with adaptive stopping the max-type trees are deeper (5.3–11.0 levels against 4.0–10.0), and with exhaustive stopping the Bonferroni trees are deeper (6.7–18.3 against 5.0–10.3). The planted signal is linear in three of the ten predictors, so depth reflects both power at small nodes and splits on noise; the real-data scores are the measure of which trees predict better.

Task	n	Bins	Adaptive		Exhaustive	
			Bonferroni	Max-type	Bonferroni	Max-type
Classification	1,000	16	0.49	0.31	0.58	0.29
	1,000	64	1.64	0.36	5.11	0.37
	1,000	256	12.6	0.36	60.0	0.50
	4,000	16	0.94	0.45	1.64	0.50
	4,000	64	5.30	0.48	25.3	0.73
	4,000	256	40.2	0.62	426	1.60
	16,000	16	3.39	0.72	6.74	1.24
	16,000	64	16.0	1.01	117	2.43
	16,000	256	134	1.61	censored	6.67
Regression	1,000	16	0.62	0.34	0.60	0.30
	1,000	64	1.26	0.40	5.27	0.37
	1,000	256	2.44	0.42	60.5	0.50
	4,000	16	1.23	0.55	2.14	0.55
	4,000	64	5.42	0.60	28.0	0.76
	4,000	256	18.7	0.76	486	1.53
	16,000	16	4.09	1.03	8.47	1.33
	16,000	64	16.9	1.35	122	2.50
	16,000	256	134	1.92	censored	6.24

Table 8: Median fitting time in seconds over three fits of one tree on ten Gaussian predictors with a planted linear signal, by Stage B construction and stopping mode, on a 32-core cloud instance. Bins is the histogram threshold setting as in Table 7. Censored marks a cell whose fits exceeded 900 seconds.

On the six real datasets (Table 9) the max-type rule gave held-out scores at least as high as the Bonferroni rule in 10 of the 12 dataset and stopping-mode cells, by 0.002 to 0.10 with exhaustive stopping and by 0.005 to 0.031 with adaptive stopping; the exceptions are page-blocks with adaptive stopping, lower by 0.002, and facebook with exhaustive stopping, where the response has a median of 123.5 and a maximum of 6,334, so a single extreme held-out observation can decide a fold’s R^2 under either rule. Its fitting time was 0.9 to 30 times shorter with adaptive stopping and 1.5 to 155 times shorter with exhaustive stopping. The Spearman agreement of the two rules’ feature importances ranges from 0.40 to 0.95, so the max-type rule produces a different ranking rather than a faster route to the same one. In the head-to-head forest timing on the recommended configuration, with both rules refit in one run, the max-type rule is 4.5–15 $\times$ faster than the per-threshold rule on synthetic Gaussian predictors at $n \in \{500, 2,000, 8,000\}$ and $p \in \{20, 100, 500\}$; on the eight real datasets it reduces madelon from 21 to 4.8 seconds, gamma from 42 to 23 seconds, and musk from 12 to 9.2 seconds, and changes the other five by less than one second.

Dataset	n	p	Adaptive				Exhaustive			
			Score		Seconds		Score		Seconds	
			Bonf.	Max-T	Bonf.	Max-T	Bonf.	Max-T	Bonf.	Max-T
vowel	990	10	0.690	0.721	3.12	0.50	0.586	0.649	60.1	0.64
spam	4,601	57	0.907	0.912	5.14	1.75	0.888	0.903	190	9.00
page-blocks	5,473	10	0.965	0.963	17.6	0.59	0.958	0.961	402	2.59
imports-85	205	76	0.745	0.773	0.66	0.57	0.573	0.676	0.71	0.45
residential	372	107	0.928	0.936	4.78	5.46	0.862	0.879	3.13	2.16
facebook	500	21	0.829	0.842	5.28	0.70	0.677	0.630	11.7	0.45

Table 9: Five-fold held-out score (accuracy for the three classification datasets, R^2 for the three regression datasets) and median fitting time in seconds of one tree at the 256-bin histogram setting, by Stage B construction (Bonf. is the per-threshold Bonferroni rule, Max-T the max-type rule) and stopping mode, on a 32-core cloud instance.

6 High-dimensional and synthetic analyses

High-dimensional real datasets. These analyses study where CIF’s scores peak as k grows, how feature recovery on synthetic datasets changes across values of k , and how feature sampling inside the forest affects how often splits use informative features. Across the 15 classification datasets with more than 100 features, CIF first reaches its best score at an intermediate value of k ($100 < k < p$) in 29 of 45 dataset-learner combinations. It first reaches its best score at the full feature set ($k = p$) in only 7 of 45 combinations. Figure 3 shows this pattern by downstream learner; regression is summarized next. Classification scores most often peak at intermediate k : 8 of 15 LR datasets, 12 of 15 SVM datasets, and 9 of 15 KNN datasets. The full feature set is mainly an LR exception. Moving from $k=100$ to $k=p$ gives a mean $k=p$ minus $k=100$ score change of $+0.026$ for LR, and $k = p$ matches the best observed LR score in 7 of 15 datasets. For SVM and KNN, the corresponding mean changes are -0.053 and -0.071 , and $k = p$ is best in only 1 of 15 datasets for each learner.

In the 6 high- p regression datasets, full-feature evaluation is rarely best. Across the 18 dataset-learner combinations, 12 peak at or below $k=100$, only 2 peak at $k = p$, and the mean $k=p$ minus $k=100$ score change is -0.270 . The main full-feature exception remains the classification LR result in Figure 3.




Figure 3: Where CIF’s classification scores peak as k increases, by downstream learner. (A) shows, for each learner, the percentage of 15 datasets where the first evaluated k attaining the best observed CIF score falls below 100, at 100, between 100 and p , or at $k=p$. (B) shows the mean balanced accuracy change from $k=100$ to $k=p$.

Synthetic feature recovery. Across synthetic classification datasets, 35.3% of the features in CIF’s top- k list are truly informative on average over the evaluated k values, ranked 8th of the 15 methods with synthetic classification runs, and its top-1 hit rate is 65.5%, ranked 10th of 15. Across synthetic regression datasets, the corresponding values are 39.1%, ranked 11th of the 16 methods with synthetic regression runs, and 84.5%, ranked 10th of 16. In both tasks, CIF recovers true features within the top- k list more reliably than it places one first. Table 10 summarizes this contrast, and Figure 4 shows recovery as k grows. The percentage of selected features that are informative falls as k grows. On redundant-feature synthetic designs, most selected features correspond to true signals or redundant proxies: 82.4% for classification and 83.8% for regression.

Metric	Classification		Regression	
	Value	Rank	Value	Rank
Selected features that are informative	35.3%	8/15	39.1%	11/16
Top-1 hit rate	65.5%	10/15	84.5%	10/16
Selected features that are true or redundant	82.4%	7.5/15	83.8%	1/16

Table 10: Synthetic feature recovery for CIF. The first row averages, over $k = 5, 10, 25, 50$, and 100, the percentage of selected features that are truly informative. The top-1 hit rate is computed at $k = 1$. The final row is computed and ranked only on the redundant-feature design for each task and counts true informative plus redundant features. Ranks are among the 15 classification and 16 regression methods with synthetic runs; fractional ranks indicate averaged ties.




Figure 4: Synthetic top- k recovery curves. Columns compare single trees, forests, and boosted trees; rows show classification and regression. Each value is the percentage of selected features that are truly informative.

Feature sampling in forests. A sparse simulation asks whether forest feature sampling makes splits less likely to use informative features in classification and regression settings. Figure 5 shows one sparse classification design comparing CIF with CIF-all. CIF samples a subset of features at each split; CIF-all considers every nonconstant feature in Stage A. Appendix H gives the classification and regression results over $p \in \{100, 500, 1,000\}$.

In the single-tree simulations, CIT uses informative features in 100.0% of classification splits and 93.5% of regression splits. In this fixed design, informative features are usually selected when every nonconstant feature is considered. In forests, sampling a subset of features reduces how often informative features are used for splits. Across the classification forest simulations with 1,000 trees, CIF uses informative features in 33.2% of splits, compared with 91.7% for CIF-all, 8.4% for RF, and 6.5% for ET. CIF also uses more distinct noise features than CIF-all, 265 versus 93 on average. For the $p=1,000$ classification setting with two informative features, CIF uses informative features in 9.0% of splits, while CIF-all uses them in 100.0%. In regression, CIF-all uses informative




Figure 5: Tree-level feature use in one sparse classification forest design ($n=250$, $p=1,000$, two informative features, 1,000 trees). Counts are the number of trees using each feature in at least one split. CIF samples a subset of features; CIF-all evaluates all nonconstant features. Each subplot has its own y-axis range because counts differ across methods.

features more often than CIF, 42.3% versus 27.8%, but uses more distinct noise features, 528.8 versus 367.7. CIF-all isolates feature subsampling because feature muting and the other tree settings are held fixed. In these sparse high- p simulations, splits use informative features most often when every nonconstant feature can enter Stage A. When the sampled feature subset rarely includes an informative feature at a node, Stage A selects from that subset.

7 Discussion

In these experiments, CIF is best supported as a top- k feature-selection method for a downstream model. The benchmark asks whether a ranking places predictive features early enough for fixed downstream learners. Classification gives the clearest support; the smaller regression panel is positive but less precise. The fixed-node Stage A theorem provides the local guarantee; fitted tree and forest rankings are assessed empirically.

Guidance. A CIF ranking should be judged through the downstream model that will use the selected features. In practice, choose k on held-out data over a small set of values that includes the intended feature budget and, when feasible, the full feature set as a sanity check. When prediction accuracy is the main target, tree-ensemble baselines such as random forests, ExtraTrees, and boosted trees should remain in the comparison set. When the target is variable screening or a ranked feature

list for later modeling, CIF should also be compared with ctree, cforest, and forest-based screening methods such as Boruta, permutation or conditional permutation importance, and RF-RFE [10].

The ablations show that adaptive stopping and histogram-256 thresholding account for the largest measured CIF runtime changes, with small downstream score changes in these experiments. Bonferroni correction is part of the Stage A testing rule and is not treated as a runtime shortcut. For ranking quality, forest size matters more than the split-count and feature-muting variants tested here, so the selected CIF configuration is the relevant ranking reference when ranking quality is the priority. The Stage B construction is a further control. The per-threshold Bonferroni rule used throughout the benchmark is valid and increasingly conservative as the candidate count grows; the max-type rule keeps the complete-node false-split rate below the nominal level at a fraction of the cost, most of all when early stopping is off, and it grows different trees. The benchmark rankings are Bonferroni rankings: the ranking benchmark was not rerun under the max-type rule, whose importance agreement with the per-threshold rule ranged from 0.40 to 0.95 on six datasets, so its effect on the full-benchmark rankings is unmeasured.

The adaptive stopping rule is a heuristic: it stops a permutation test once a Beta posterior on the exceedance proportion places probability at least 0.95 on one side of the significance level, and no level theorem exists for it. Simulation shows approximately nominal null rejection at the default confidence. A theorem-backed replacement is available in the sequential Monte Carlo rule of Gandy [9] and in time-uniform confidence sequences for a proportion [20, 34], which bound the probability that early stopping alters the fixed-budget decision; we leave its implementation to future work.

In sparse high- p settings, feature use should be monitored directly. The simulations show that CIF feature sampling can leave informative features out of many forest split decisions, especially in sparse classification designs. Useful diagnostics include top- k stability across seeds, the share of splits using the final top- k features or any prespecified positive control features, the number of distinct low-ranked or known null features used in splits, and sensitivity to larger sampled feature sets or to a small CIF-all run with fewer seeds or trees.

Limitations. The fixed-node result is a reference guarantee for exhaustive fixed- B Stage A testing at one node, with the tested features and permutation budget fixed independently of the node responses. The benchmarked trees and forests add adaptive stopping, feature and threshold ordering, feature muting, bounded threshold sets, bootstrap samples, and forest aggregation, so their behavior is assessed through the ranking benchmark.

The benchmark coverage is uneven across analyses. Some comparisons use broader panels where both methods are available, while complete-case rank and interval summaries use smaller panels that include every method. These summaries are therefore descriptive rather than confirmatory.

The sampled-forest analysis isolates a sparse high- p setting in which forest feature sampling can limit how often splits use informative features: larger sampled feature sets increase informative-feature use, but they also change runtime and the mix of noise features used by splits. Track how often splits use informative features alongside downstream performance and runtime before changing the number of features sampled at each split.

8 Conclusion

This paper evaluates conditional-inference tree and forest rankings for top- k downstream prediction and proves a fixed-node guarantee for Stage A permutation testing. The experiments support CIF as a top- k feature-ranking method, especially in classification: its rankings compare favorably with ctree, cforest, and CIT, and they remain competitive among stronger tree-ensemble baselines.

The ablations separate runtime and ranking effects. Adaptive stopping and bounded threshold search avoid large runtime increases, while the one-tree ablation has the largest ranking-quality loss. The high- p and synthetic analyses add two diagnostic cautions: sparse forests should be checked for whether informative features are used in enough splits to enter the top- k ranking, and CIF should not be treated as a first-feature discovery method when the goal is to identify a single driver. Overall, these results support CIF as a feature-ranking method for downstream prediction, backed by a local Stage A result and benchmark evidence.

References

- [1] Susan Athey, Julie Tibshirani, and Stefan Wager. Generalized random forests. *The Annals of Statistics*, 47(2):1148–1178, 2019. doi: 10.1214/18-AOS1709.
- [2] Julian Besag and Peter Clifford. Sequential Monte Carlo p-values. *Biometrika*, 78(2):301–304, 1991. doi: 10.1093/biomet/78.2.301.
- [3] Leo Breiman. Random forests. *Machine Learning*, 45(1):5–32, 2001. doi: 10.1023/A:1010933404324.
- [4] Leo Breiman, Jerome H. Friedman, Charles J. Stone, and Richard A. Olshen. *Classification and Regression Trees*. Wadsworth International Group, Belmont, CA, 1984. ISBN 9780412048418.
- [5] Tianqi Chen and Carlos Guestrin. A scalable tree boosting system. In *Proceedings of the 22nd ACM SIGKDD International Conference on Knowledge Discovery and Data Mining*, pages 785–794, 2016. doi: 10.1145/2939672.2939785.
- [6] Dries Debeer and Carolin Strobl. Conditional permutation importance revisited. *BMC Bioinformatics*, 21(1):307, 2020. doi: 10.1186/s12859-020-03622-2.
- [7] Ozgur Demir-Kavuk, Henning Riedesel, and Ernst-Walter Knapp. Exploring classification strategies with the CoEPrA 2006 contest. *Bioinformatics*, 26(5):603–609, 2010. doi: 10.1093/bioinformatics/btq021.
- [8] Michael D. Ernst. Permutation methods: A basis for exact inference. *Statistical Science*, 19(4): 676–685, 2004. doi: 10.1214/088342304000000396.
- [9] Axel Gandy. Sequential implementation of Monte Carlo tests with uniformly bounded resampling risk. *Journal of the American Statistical Association*, 104(488):1504–1511, 2009. doi: 10.1198/jasa.2009.tm08368.
- [10] Robin Genuer, Jean-Michel Poggi, and Christine Tuleau-Malot. Variable selection using random forests. *Pattern Recognition Letters*, 31(14):2225–2236, 2010. doi: 10.1016/j.patrec.2010.03.014.
- [11] Pierre Geurts, Damien Ernst, and Louis Wehenkel. Extremely randomized trees. *Machine Learning*, 63(1):3–42, 2006. doi: 10.1007/s10994-006-6226-1.
- [12] Isabelle Guyon, Jason Weston, Stephen Barnhill, and Vladimir Vapnik. Gene selection for cancer classification using support vector machines. *Machine Learning*, 46(1-3):389–422, 2002. doi: 10.1023/A:1012487302797.

- [13] Isabelle Guyon, Steve Gunn, Asa Ben-Hur, and Gideon Dror. Result analysis of the NIPS 2003 feature selection challenge. In *Advances in Neural Information Processing Systems*, volume 17, 2004. URL https://proceedings.neurips.cc/paper_files/paper/2004/hash/5e751896e527c862bf67251a474b3819-Abstract.html.
- [14] Jesse Hemerik and Jelle Goeman. Exact testing with random permutations. *TEST*, 27(4): 811–825, 2018. doi: 10.1007/s11749-017-0571-1.
- [15] Torsten Hothorn and Achim Zeileis. partykit: A modular toolkit for recursive partytioning in R. *Journal of Machine Learning Research*, 16(118):3905–3909, 2015. URL <https://jmlr.org/papers/v16/hothorn15a.html>.
- [16] Torsten Hothorn, Peter Bühlmann, Sandrine Dudoit, Annette Molinaro, and Mark J. van der Laan. Survival ensembles. *Biostatistics*, 7(3):355–373, 2006. doi: 10.1093/biostatistics/kxj011.
- [17] Torsten Hothorn, Kurt Hornik, Mark A. van de Wiel, and Achim Zeileis. A lego system for conditional inference. *The American Statistician*, 60(3):257–263, 2006. doi: 10.1198/000313006X118430.
- [18] Torsten Hothorn, Kurt Hornik, and Achim Zeileis. Unbiased recursive partitioning: A conditional inference framework. *Journal of Computational and Graphical Statistics*, 15(3):651–674, 2006. doi: 10.1198/106186006X133933.
- [19] Torsten Hothorn, Heidi Seibold, and Achim Zeileis. *partykit: A Toolkit for Recursive Partitioning*, 2026. URL <https://CRAN.R-project.org/package=partykit>. R package version 1.2-27.
- [20] Steven R. Howard, Aaditya Ramdas, Jon McAuliffe, and Jasjeet Sekhon. Time-uniform, nonparametric, nonasymptotic confidence sequences. *The Annals of Statistics*, 49(2):1055–1080, 2021. doi: 10.1214/20-AOS1991.
- [21] Guolin Ke, Qi Meng, Thomas Finley, Taifeng Wang, Wei Chen, Weidong Ma, Qiwei Ye, and Tie-Yan Liu. A highly efficient gradient boosting decision tree. In *Advances in Neural Information Processing Systems*, volume 30, pages 3146–3154, 2017. URL <https://papers.nips.cc/paper/6907-a-highly-efficient-gradient-boosting-decision-tree>.
- [22] Markelle Kelly, Rachel Longjohn, and Kolby Nottingham. UCI machine learning repository. <https://archive.ics.uci.edu>, n.d. URL <https://archive.ics.uci.edu/>. Accessed 2026-05-04.
- [23] Hyunjoong Kim and Wei-Yin Loh. Classification trees with unbiased multiway splits. *Journal of the American Statistical Association*, 96(454):589–604, 2001. doi: 10.1198/016214501753168271.
- [24] Miron B. Kursa and Witold R. Rudnicki. Feature selection with the Boruta package. *Journal of Statistical Software*, 36(11):1–13, 2010. doi: 10.18637/jss.v036.i11.
- [25] Jundong Li, Kewei Cheng, Suhang Wang, Fred Morstatter, Robert P. Trevino, Jiliang Tang, and Huan Liu. Feature selection: A data perspective. *ACM Computing Surveys*, 50(6):94:1–94:45, 2018. doi: 10.1145/3136625.
- [26] Wei-Yin Loh. Regression trees with unbiased variable selection and interaction detection. *Statistica Sinica*, 12(2):361–386, 2002. URL <https://www3.stat.sinica.edu.tw/statistica/j12n2/j12n21/j12n21.htm>.

- [27] Wei-Yin Loh and Yu-Shan Shih. Split selection methods for classification trees. *Statistica Sinica*, 7(4):815–840, 1997. URL <https://www3.stat.sinica.edu.tw/statistica/j7n4/j7n41/j7n41.htm>.
- [28] David Lopez-Paz, Philipp Hennig, and Bernhard Schölkopf. The randomized dependence coefficient, 2013. arXiv:1304.7717.
- [29] B. V. North, David Curtis, and Pak C. Sham. A note on the calculation of empirical P values from Monte Carlo procedures. *American Journal of Human Genetics*, 71(2):439–441, 2002. doi: 10.1086/341527.
- [30] Fabian Pedregosa, Gaël Varoquaux, Alexandre Gramfort, Vincent Michel, Bertrand Thirion, Olivier Grisel, Mathieu Blondel, Peter Prettenhofer, Ron Weiss, Vincent Dubourg, Jake VanderPlas, Alexandre Passos, David Cournapeau, Matthieu Brucher, Matthieu Perrot, and Édouard Duchesnay. Scikit-learn: Machine learning in Python. *Journal of Machine Learning Research*, 12(85):2825–2830, 2011. URL <https://jmlr.org/papers/v12/pedregosa11a.html>.
- [31] Belinda Phipson and Gordon K. Smyth. Permutation P-values should never be zero: Calculating exact P-values when permutations are randomly drawn. *Statistical Applications in Genetics and Molecular Biology*, 9(1):1–12, 2010. doi: 10.2202/1544-6115.1585.
- [32] Katherine S. Pollard and Mark J. van der Laan. Choice of a null distribution in resampling-based multiple testing. *Journal of Statistical Planning and Inference*, 125(1–2):85–100, 2004. doi: 10.1016/j.jspi.2003.07.019.
- [33] Liudmila Ostroumova Prokhorenkova, Gleb Gusev, Aleksandr Vorobev, Anna Veronika Dorogush, and Andrey Gulin. Unbiased boosting with categorical features. In *Advances in Neural Information Processing Systems*, volume 31, pages 6639–6649, 2018. URL <https://papers.nips.cc/paper/7898-catboost-unbiased-boosting-with-categorical-features>.
- [34] Herbert Robbins. Statistical methods related to the law of the iterated logarithm. *The Annals of Mathematical Statistics*, 41(5):1397–1409, 1970. doi: 10.1214/aoms/1177696786.
- [35] Yu-San Shih. A note on split selection bias in classification trees. *Computational Statistics & Data Analysis*, 45(3):457–466, 2004. doi: 10.1016/S0167-9473(03)00064-1.
- [36] Helmut Strasser and Christian Weber. The asymptotic theory of permutation statistics. *Mathematical Methods of Statistics*, 8(2):220–250, 1999.
- [37] Carolin Strobl, Anne-Laure Boulesteix, and Thomas Augustin. Unbiased split selection for classification trees based on the Gini index. *Computational Statistics & Data Analysis*, 52(1):483–501, 2007. doi: 10.1016/j.csda.2006.12.030.
- [38] Carolin Strobl, Anne-Laure Boulesteix, Achim Zeileis, and Torsten Hothorn. Bias in random forest variable importance measures: Illustrations, sources and a solution. *BMC Bioinformatics*, 8(1):25, 2007. doi: 10.1186/1471-2105-8-25.
- [39] Carolin Strobl, Anne-Laure Boulesteix, Thomas Kneib, Thomas Augustin, and Achim Zeileis. Conditional variable importance for random forests. *BMC Bioinformatics*, 9(1):307, 2008. doi: 10.1186/1471-2105-9-307.

- [40] Gábor J. Székely, Maria L. Rizzo, and Nail K. Bakirov. Measuring and testing dependence by correlation of distances. *The Annals of Statistics*, 35(6):2769–2794, 2007. doi: 10.1214/009053607000000505.
- [41] Joaquin Vanschoren, Jan N. van Rijn, Bernd Bischl, and Luis Torgo. OpenML: Networked science in machine learning. *ACM SIGKDD Explorations Newsletter*, 15(2):49–60, 2013. doi: 10.1145/2641190.2641198. URL <https://doi.org/10.1145/2641190.2641198>.
- [42] Stefan Wager and Susan Athey. Estimation and inference of heterogeneous treatment effects using random forests. *Journal of the American Statistical Association*, 113(523):1228–1242, 2018. doi: 10.1080/01621459.2017.1319839.
- [43] Peter H. Westfall and S. Stanley Young. *Resampling-Based Multiple Testing: Examples and Methods for P-Value Adjustment*. Wiley, New York, 1993. ISBN 0471557617.

Appendix A Setup and assumptions

A.1 Fixed-node setup

Let $(X_i, Y_i)_{i=1}^n$ be the training data. Fix a node t with sample index set I_t and size $n_t := |I_t|$. Write $X_t := (X_i)_{i \in I_t}$ and $Y_t := (Y_i)_{i \in I_t}$ for the data restricted to that node. Stage A tests features F_t with $m_t := |F_t|$.

The fixed-node theorem analyzes the exhaustive fixed- B Stage A reference test. Conditional on the node covariates and label-independent auxiliary randomness U , F_t and B are fixed, and every feature in F_t is tested with exactly B permutations.

Notation

Table 11 lists the notation used in the proof.

Symbol	Meaning
t	Node index, held fixed in the theorem.
I_t, n_t	Node sample index set and size $n_t := I_t $.
X_t, Y_t	Covariates and labels restricted to node t .
U	Label-independent auxiliary randomness conditioned on in the proof; it excludes node responses, Monte Carlo permutation draws, permutation statistics, and p -values.
F_t, m_t	Stage A features and size $m_t := F_t $.
$X_{t,j}$	Values of feature j on the node samples.
B	Number of random label permutations per tested feature in the fixed- B reference test.
T_j^{sel}	Stage A selector statistic for feature j : $T_j^{\text{sel}}(X_{t,j}, Y_t; U)$.
$T(\cdot, \cdot; U)$	Generic scalar test statistic used in the exchangeability proof.
Π_b	Random label permutation used for Monte Carlo replicate b .
$T_{\text{obs}}, T_1, \dots, T_B$	Observed and permuted statistics for one fixed feature test.
R	Right-tail rank numerator $1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_{\text{obs}}\}$.
$p_{\text{MC}}^{\geq}$	Right-tail +1 Monte Carlo permutation p -value for one fixed feature test.
$p_{t,j}$	Fixed- B +1 Monte Carlo permutation p -value for feature j .
α_{sel}	Stage A nominal level; the corollary tests at α_{sel}/m_t .

Table 11: Notation used in the fixed-node Stage A theorem and proof.

The guarantee applies to fixed-node, fixed- B tests: the Stage A feature tests and, in Corollary 2, the max-type Stage B test for a feature and candidate set fixed without reference to the responses. It does not cover the per-threshold Stage B search, adaptive stopping, response-dependent feature muting, response-selected internal nodes, bootstrap forests, honesty, or p -values after feature selection or other post-selection steps; see Section 2 and Appendices D and E.

A.2 Assumptions and theorem scope

A0.1 (Fixed node). Assumptions A0.1–A0.5 define the fixed-node reference setting used by Theorem 1 and Corollary 1. The node t and its sample index set I_t are held fixed for the result. They are not chosen using node responses or earlier response-dependent splits.

A0.2 (Complete nodewise permutation null). Under the complete null at node t , Y_t is exchangeable conditional on (X_t, U) : its conditional law is unchanged by permuting the node

responses. This complete nodewise permutation null does not cover a null feature when any tested or untested node covariate remains associated with Y_t .

A0.3 (Features fixed before seeing node responses). The features in F_t and the effective nodewise budget B are measurable functions of (X_t, U) only. They do not depend on Y_t , other training responses used to reach the node, Monte Carlo permutation draws or statistics, p -values, or sequential stopping decisions.

A0.4 (Fixed- B computation). Each $p_{t,j}$ is computed with exactly B random permutations, with no optional stopping. The Monte Carlo permutation draws used to compute the p -values are additional randomness, independent of (X_t, Y_t, U) , and are not included in U .

A0.5 (Conservative ties). For right-tail tests, the Stage A +1 Monte Carlo p -value counts ties conservatively using $\mathbf{1}\{T_b \geq T_{\text{obs}}\}$; left-tail tests, including the max-type Stage B test, use $\mathbf{1}\{T_b \leq T_{\text{obs}}\}$. If several features tie after testing, any random tie break is label-independent and does not affect the Stage A reject/no-reject event.

A.3 Results using these assumptions

The fixed-node results in Section 3 use Assumptions A0.1–A0.5. Theorem 1 proves +1 Monte Carlo permutation p -value superuniformity. Corollary 1 gives Stage A complete-null control, and Corollary 2 gives complete-null control for the max-type Stage B test at a fixed node.

Appendix B Monte Carlo permutation exchangeability

The proof separates two facts. First, statistics computed from i.i.d. random permutations are exchangeable. Second, under A0.2–A0.4, the usual “observed statistic + B random permutations” computation has the same null rank distribution as a construction with a randomized baseline. The superuniformity proof then uses the conservative tie convention in A0.5; see also Hemerik and Goeman [14] for a broader treatment of exact random permutation testing.

First consider a fully randomized tuple. Fix a node t , feature j , and a real-valued statistic $T(\cdot, \cdot; U)$ with a right tail convention (larger is more extreme), where U denotes label-independent auxiliary randomness. Let $\Pi_0, \Pi_1, \dots, \Pi_B$ be i.i.d. uniform random permutations of $\{1, \dots, n_t\}$, independent of the data (and of U), and define

$$T_b := T(X_{t,j}, \Pi_b(Y_t); U) \quad (b = 0, 1, \dots, B). \quad (9)$$

Lemma 1 (Exchangeability of Monte Carlo permutation statistics). *Conditional on (X_t, Y_t, U) , the vector $(T_0, T_1, \dots, T_B)$ is exchangeable. Averaging over Y_t preserves exchangeability, so the vector is also exchangeable conditional on (X_t, U) and unconditionally.*

Proof. Conditional on (X_t, Y_t, U) , each T_b is a measurable function of Π_b , and $(\Pi_0, \dots, \Pi_B)$ are i.i.d. Thus any permutation of the indices $b \in \{0, \dots, B\}$ leaves the joint law unchanged. $\square$

Lemma 2 (The observed statistic has the same null rank distribution). *Assume A0.2–A0.4 (Appendix A.2). Let $\Pi_1, \dots, \Pi_B$ be i.i.d. uniform random permutations of $\{1, \dots, n_t\}$, independent of (X_t, Y_t, U) . Define the observed statistic and permuted statistics by*

$$T_{\text{obs}} := T(X_{t,j}, Y_t; U), \quad T_b := T(X_{t,j}, \Pi_b(Y_t); U) \quad (b = 1, \dots, B), \quad (10)$$

and the standard +1 Monte Carlo p -value (right tail) by

$$p_{\text{id}} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_{\text{obs}}\}}{B + 1}. \quad (11)$$

Let Π_0 be an additional independent uniform random permutation and set $T_0 := T(X_{t,j}, \Pi_0(Y_t); U)$ (keeping $T_1, \dots, T_B$ as above), and define

$$p_{\text{rnd}} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_0\}}{B + 1}. \quad (12)$$

Both quantities use the same conservative right-tail tie convention: ties with the baseline statistic are counted as exceedances. Under the null, conditional on (X_t, U) , p_{id} and p_{rnd} have the same distribution with this convention. It is enough to prove the rank bound for the exchangeable construction p_{rnd} and apply the same conclusion to the standard “observed statistic + B random permutations” computation.

Proof. Fix (X_t, U) and work under the null. By A0.2, permuting the node labels does not change the conditional distribution of Y_t . Use the permutation-action convention under which $(\Pi_b \circ \Pi_0^{-1})(\Pi_0(Y_t)) = \Pi_b(Y_t)$. Let Π_0 be an independent uniform permutation and set $Y'_t := \Pi_0(Y_t)$. Then $Y'_t \stackrel{d}{=} Y_t$ conditional on (X_t, U) .

For $b = 1, \dots, B$, define $\Pi'_b := \Pi_b \circ \Pi_0^{-1}$, so $\Pi'_b(Y'_t) = \Pi_b(Y_t)$. Conditional on (Y_t, Π_0) , right composition by Π_0^{-1} maps the independent uniform permutations Π_b to independent uniform permutations Π'_b . This conditional law does not depend on the conditioning values. Because Y'_t is a function of (Y_t, Π_0) , the transformed permutations are independent of (Y'_t, Π_0) . Therefore,

$$\begin{aligned} (T_{\text{obs}}, T_1, \dots, T_B) &= (T(X_{t,j}, Y_t; U), T(X_{t,j}, \Pi_1(Y_t); U), \dots, T(X_{t,j}, \Pi_B(Y_t); U)) \\ &\stackrel{d}{=} (T(X_{t,j}, Y'_t; U), T(X_{t,j}, \Pi'_1(Y'_t); U), \dots, T(X_{t,j}, \Pi'_B(Y'_t); U)) \\ &= (T_0, T_1, \dots, T_B), \end{aligned} \quad (13)$$

where $\stackrel{d}{=}$ is conditional on (X_t, U) . Applying the same $\geq$ comparison map to these equal-in-distribution vectors gives the same conditional distribution for p_{id} and p_{rnd} . $\square$

Appendix C Proof of Theorem 1

Appendix B reduces the usual computation with one observed statistic and B random permutations to the exchangeable rank construction. We prove Theorem 1 under A0.1–A0.5 (Appendix A.2).

Fix (X_t, U) , fix one feature $j \in F_t$, and work under the nodewise complete permutation null at the fixed node t . Under A0.2–A0.4, the standard fixed- B computation has the same conditional p -value distribution as the randomized exchangeable construction; see Lemma 2 in Appendix B and Hemerik and Goeman [14]. It is enough to prove the rank bound for an exchangeable tuple, which we denote by $(T_{\text{obs}}, T_1, \dots, T_B)$.

Define the conservative right-tail rank numerator

$$R := 1 + \sum_{b=1}^B \mathbf{1}\{T_b \geq T_{\text{obs}}\}, \quad p_{\text{MC}}^{\geq} = \frac{R}{B + 1}. \quad (14)$$

The left-tail version replaces the exceedance check by $\mathbf{1}\{T_b \leq T_{\text{obs}}\}$; equivalently, apply the right-tail argument below to $-T$. Stage B uses this left-tail convention for split scores after Stage A selects a feature, but the fixed-node Type I error guarantee here concerns Stage A.

No ties. If the statistics almost surely have no ties, then the $\geq$ indicator is the same as $>$, and R is the descending rank of T_{obs} among $(T_{\text{obs}}, T_1, \dots, T_B)$, with rank 1 assigned to the largest statistic. Exchangeability implies

$$\mathbb{P}(R = r \mid X_t, U) = \frac{1}{B+1}, \quad r = 1, \dots, B+1, \quad (15)$$

so for any $\alpha \in [0, 1]$,

$$\mathbb{P}(p_{\text{MC}}^{\geq} \leq \alpha \mid X_t, U) = \mathbb{P}(R \leq (B+1)\alpha \mid X_t, U) = \frac{\lfloor (B+1)\alpha \rfloor}{B+1} \leq \alpha. \quad (16)$$

Ties. If ties can occur, A0.5 uses conservative tie handling: the right-tail $+1$ p -value uses $\mathbf{1}\{T_b \geq T_{\text{obs}}\}$, so ties with the observed statistic are counted in the numerator. To compare this rule with a no-ties rank, let $V_{\text{obs}}, V_1, \dots, V_B \stackrel{\text{i.i.d.}}{\sim} \text{Unif}(0, 1)$ be independent of all other randomness and define augmented statistics $\tilde{T}_{\text{obs}} := (T_{\text{obs}}, V_{\text{obs}})$ and $\tilde{T}_b := (T_b, V_b)$ for $b = 1, \dots, B$. Order the augmented pairs lexicographically for the right tail: $\tilde{T}_b$ exceeds $\tilde{T}_{\text{obs}}$ exactly when $T_b > T_{\text{obs}}$, or when $T_b = T_{\text{obs}}$ and $V_b > V_{\text{obs}}$. Then $(\tilde{T}_{\text{obs}}, \tilde{T}_1, \dots, \tilde{T}_B)$ is exchangeable and almost surely has no ties, so the no-ties argument gives a superuniform p -value

$$\tilde{p}_{\text{MC}}^{\geq} := \frac{1 + \sum_{b=1}^B \mathbf{1}\{T_b > T_{\text{obs}} \text{ or } (T_b = T_{\text{obs}} \text{ and } V_b > V_{\text{obs}})\}}{B+1}. \quad (17)$$

Moreover, each tie-broken indicator in $\tilde{p}_{\text{MC}}^{\geq}$ is bounded by the corresponding conservative indicator $\mathbf{1}\{T_b \geq T_{\text{obs}}\}$. Thus $p_{\text{MC}}^{\geq} \geq \tilde{p}_{\text{MC}}^{\geq}$, and

$$\mathbb{P}(p_{\text{MC}}^{\geq} \leq \alpha \mid X_t, U) \leq \mathbb{P}(\tilde{p}_{\text{MC}}^{\geq} \leq \alpha \mid X_t, U) \leq \alpha. \quad (18)$$

Taking expectations over (X_t, U) gives the unconditional bound, $\mathbb{P}(p_{\text{MC}}^{\geq} \leq \alpha) \leq \alpha$. The fixed-node Stage A corollary applies this single-test bound to the m_t feature tests with threshold α_{sel}/m_t and uses the Bonferroni union bound; no independence among feature tests is required.

Appendix D Algorithm and reproducibility notes

Algorithm settings, benchmark configuration, and coverage rules determine how the main results should be read. Section 2 describes the tree-growing loop, the setup and proof appendices state the fixed-node results, and Appendix E gives runtime and memory details for the benchmarked tree-growing algorithm.

D.1 Scope relative to the theory

The fixed-node theorem covers exhaustive fixed- B Stage A feature selection at a fixed node under the complete permutation null. In that result, the tested features and resample budget are fixed independently of the node responses. The benchmarked tree-growing algorithm also uses settings outside that theorem:

- early stopping,
- feature and threshold ordering inside early stopping,
- response-dependent feature muting,

- bounded threshold sets,
- bootstrap resampling and forest aggregation,
- optional honesty.

Under these conditions, the theorem covers exhaustive fixed- B Stage A values. Stage A and split scores from adaptive trees are tree-construction scores.

D.2 Node-level choices

Stage A. At each node, the tree-growing rule removes features that are constant on the node before any feature subsampling. Stage A computes +1 Monte Carlo p -values. It may scan features in preliminary-score order and, under early stopping, may stop once a feature meets the nodewise threshold. With feature muting, features with non-rejecting Stage A values can be removed from descendant feature pools in the same subtree. These shortcuts reduce computation. When they are active, the returned q_t^{feat} is the feature-selection score used to grow the tree; the exhaustive fixed- B reference value is defined over the full feature pool.

Stage B. After Stage A selects a feature, Stage B builds thresholds from midpoints between consecutive unique feature values. Exact search tests all midpoints. Random sampling tests a bounded subset; percentile and histogram rules test bounded representative thresholds from the midpoint distribution. With sequential stopping, Stage B may scan thresholds in a reordered sequence. Because Stage B tests thresholds only after a response-selected feature is chosen, q_t^{split} is a split-selection score.

Split statistics. For permutation split testing, Stage B uses weighted child impurity as the tested statistic and a left tail convention. The final minimum impurity-decrease filter uses the corresponding weighted impurity decrease. These quantities support split construction.

D.3 Permutation budgets and early stopping

Both stages use Phipson–Smyth +1 Monte Carlo tail estimates [31]: right-tailed in Stage A and left-tailed in Stage B. For the benchmarked CIT and CIF configurations, the resampling budget is set from the Bonferroni-adjusted nodewise threshold and is large enough for rejection to be possible on the discrete +1 scale.

Sequential stopping. The benchmarked CIT and CIF configurations use adaptive sequential stopping. The stopping rule monitors permutation exceedances and stops once a Beta posterior places the configured confidence on one side of the nodewise threshold. Because the returned values are stopping-time estimates, the paper treats the fixed-node guarantee and runtime ablations separately.

D.4 Forests, resampling, and honesty

CIF fits bootstrap trees and forms feature rankings by aggregating tree split-importance vectors. The benchmark uses stratified bootstrap sampling for classification and standard bootstrap sampling for regression. These forest-level choices affect the fitted rankings, while the fixed-node theorem covers only the Stage A reference test.

D.5 Benchmark coverage

Sections 4.1 and 4.5 define the benchmark protocol and configuration-selection rule. The benchmark compares 17 classification methods and 18 regression methods, including permutation-test filters, embedded tree and ensemble methods, R ctree/cforest, and wrapper methods. The rules below define which runs enter the appendix tables.

For per-method and direct pairwise summaries, each comparison uses the datasets, downstream learners, and standard values of k where the methods in that comparison are present. Analyses that compare all methods restrict to datasets with every method, downstream learner, and standard value of k present. These rules give 13 classification and 6 regression datasets for complete-case analyses. On `gisette`, `isolet`, and `orlraws10P`, 34 classification runs were excluded from the benchmark for operational reasons: 15 partykit ctree and cforest runs inherited from the earlier compute campaign did not complete on those datasets, and 19 RDC-selector CIT and CIF runs on the same datasets were excluded by author direction. Comparisons that involve an affected method on an affected dataset use the remaining datasets. Table 12 lists the excluded runs.

D.6 Randomness and reproducibility

The benchmark configuration fixes the seed schedule used for all reported runs. Pure Python permutation routines use local `numpy` generators. Numba parallel permutation paths assign one seed per resample, which avoids sharing a mutable generator across parallel loop iterations.

Dataset	Method	Configurations	Seed runs	Basis
<code>gisette</code>	CIT with selector <code>rdc</code>	2	8	author directed
<code>gisette</code>	R ctree	1	5	inherited
<code>isolet</code>	CIF with selector <code>rdc</code>	2	4	author directed
<code>isolet</code>	CIT with selector <code>rdc</code>	2	6	author directed
<code>isolet</code>	R cforest	1	5	inherited
<code>isolet</code>	R ctree	1	5	inherited
<code>orlraws10P</code>	CIT with selector <code>rdc</code>	1	1	author directed

Table 12: Classification benchmark exclusions. Each seed run is one method configuration on one dataset with one seed; 34 runs are excluded in total, and all are operational exclusions. Inherited rows are partykit ctree and cforest runs that did not complete in the earlier compute campaign; author-directed rows are RDC-selector CIT and CIF runs excluded by author direction. No regression runs are excluded.

Appendix E Runtime and memory accounting

The runtime terms behind the ablations in Section 5.2 are counted node by node: the scans, copies, and feature or threshold tests actually reached. A node-by-node sum is needed because feature pools, node sizes, threshold counts, and stopping times vary across the tree.

Let n be the training sample count and let p be the number of features. At node t , let n_t be the number of samples reaching the node. Using the notation of Section 2.1, write $a_t = |F_{t,\text{avail}}|$ and $d_t^{\text{const}} = |F_{t,\text{avail}} \setminus F_{t,\text{nonconst}}|$. After constant feature pruning and any feature subsampling, Stage A considers F_t , with $m_t = |F_t|$. Let d_t^{mute} be the number of tested Stage A features removed from the descendant feature pool by feature muting; if feature muting is disabled, $d_t^{\text{mute}} = 0$.

Stage B is reached only when Stage A returns a selected feature j_t^* : either the Stage A permutation feature test rejects or selector permutation testing is disabled. If Stage B is reached, let $\tilde{h}_t$ be the

number of thresholds generated for j_t^* before any minimum leaf size filtering. Let $h_t = |C_{t,j_t^*}| \leq \tilde{h}_t$ be the number of valid thresholds that remain after this filtering; if no filtering is applied, $h_t = \tilde{h}_t$.

Let $C_j^{\text{sel}}(n_t)$ be the cost of the Stage A statistic for feature j at node size n_t , excluding the label copies and shuffles counted separately below. For a list of selectors, this denotes the cost of evaluating the selector statistics for one observed or permuted draw and taking their common-scale maximum. Let $C^{\text{split}}(n_t)$ be the cost of one Stage B impurity statistic after the threshold mask and child-label slices have been formed; the mask, slice, label shuffle, and copy overhead is counted separately below. For the multiple-correlation selector with Gini splitting in classification and the Pearson-correlation selector with MSE splitting in regression, these statistic evaluations are linear in n_t for a fixed number of classes. The randomized dependence coefficient (RDC) is $O(n_t \log n_t)$ for fixed random-projection and class counts. For distance correlation and mutual information, the cost depends on the backend used by $C_j^{\text{sel}}(n_t)$: distance correlation may cost $O(n_t \log n_t)$ or $O(n_t^2)$, and mutual information is delegated to scikit-learn.

How runtime hyperparameters enter the accounting.

- **Feature subsampling.** This caps m_t and therefore the Stage A testing width. It does not cap the constant feature preprocessing pass over all a_t available features. Feature-set construction and random ordering add at most linear overhead in the local available feature count.
- **Feature muting.** This can shrink a_u and m_u at descendant nodes u . It can also add $O(a_t d_t^{\text{mute}})$ feature index updates at the current node when tested features whose Stage A p -values do not reject are removed.
- **Threshold-search method and threshold cap.** Non-exact threshold methods can reduce the returned pre-filter threshold set $\tilde{h}_t$ when the configured cap is active. Exact search and the fallback for features with at most four unique values use all midpoints.
- **Adaptive stopping, feature scanning, and threshold scanning.** These reduce work only when they shorten the actual stopping path. They may change feature or threshold order and reduce the number of tested features, tested thresholds, or permutation draws, but the worst case is still all features or thresholds and the full budget. Bonferroni is separate because it changes the statistical rule.
- **Bonferroni correction and resampling presets.** When Bonferroni correction is enabled, the nodewise threshold is divided by the number of tests in that stage. Write r_{tests} for this count (m_t in Stage A and h_t in Stage B) and $\alpha_{\text{stage}} \in \{\alpha_{\text{sel}}, \alpha_{\text{split}}\}$ for the corresponding nominal level. Named resampling presets compute the permutation budget at the stricter threshold $\alpha_{\text{stage}}/r_{\text{tests}}$: the *minimum* budget scales like $r_{\text{tests}}/\alpha_{\text{stage}}$, the *maximum* budget is $\lceil r_{\text{tests}}^2/(4\alpha_{\text{stage}}^2) \rceil$ up to rounding, and *auto* uses the same stricter threshold in its normal-quantile formula. For an explicit integer budget, the budget is multiplied by r_{tests} .
- **Bootstrap sample size, forest size, and worker count.** The bootstrap sample-size control affects the requested or capped bootstrap sample size, the forest size sets the number of tree fits, and the worker count affects parallel scheduling and memory pressure.

Per-node accounting. At each node, the tree builder first checks whether it must stop, including whether all labels are equal, and computes the leaf value if it stops. This costs $O(n_t)$ at every node.

If the node can split, the builder scans all available features and removes features that are constant at the node. This costs $O(a_t n_t)$ for the data scan. Updating the array of available feature indices costs another $O(a_t d_t^{\text{const}})$ for constant feature removals in the dense matrix algorithm, with worst case $O(a_t^2)$ if many available features are constant at the same node. This pruning occurs before feature subsampling, so subsampling caps Stage A width but not the initial constant feature scan.

Let $\mathcal{J}_t$ be the Stage A features whose score or permutation test is evaluated before any feature-level early stop. With Stage A permutation tests, this is the evaluated subset E_t from Section 2.1. It does not include the optional feature-scanning prescan, which is counted separately. Let $b_{t,j}^{\text{sel}}$ be the number of permutation draws actually used for feature j ; when permutation tests are not run, take $b_{t,j}^{\text{sel}} = 0$. The Stage A testing work is

$$S_t^A = O\left(\sum_{j \in \mathcal{J}_t} (b_{t,j}^{\text{sel}} + 1)(C_j^{\text{sel}}(n_t) + n_t)\right), \quad (19)$$

where the $+1$ accounts for the observed statistic and the n_t term accounts for label copies, shuffles, and other per-draw linear overhead inside the permutation test. Feature scanning, when enabled with selector early stopping, computes prescan scores and sorts features, adding

$$G_t^A = O\left(\sum_{j \in F_t} C_j^{\text{scan}}(n_t) + m_t \log m_t\right), \quad (20)$$

where C_j^{scan} is the selector-score cost used for ordering. If feature muting removes tested features whose Stage A p -values do not reject, updating the descendant available feature array adds $O(a_t d_t^{\text{mute}})$ work at the current node.

Stage B first builds thresholds for the selected feature. An upper bound is $O(n_t \log n_t)$, because unique values are computed and sorted before threshold caps are applied. If the minimum leaf size is greater than one, filtering adds $O(n_t \log n_t + \tilde{h}_t \log n_t)$ for the feature sort and threshold lookups. Bounded non-exact methods reduce $\tilde{h}_t$ only when the effective cap is below the number of available midpoints; with few unique values or no effective cap, all available midpoints can remain in the threshold set. They do not remove the initial unique-value pass.

Let $\mathcal{C}_t^{\text{eval}} \subseteq \mathcal{C}_{t,j^*}$ be the retained Stage B thresholds whose permutation test or non-permutation split score is evaluated before any threshold-level early stop. Let $b_{t,c}^{\text{split}}$ be the corresponding realized permutation count; when splitter permutation tests are not run, take $b_{t,c}^{\text{split}} = 0$. The Stage B testing work is

$$S_t^B = O\left(\sum_{c \in \mathcal{C}_t^{\text{eval}}} (b_{t,c}^{\text{split}} + 1)(C^{\text{split}}(n_t) + n_t)\right). \quad (21)$$

In S_t^B , the added n_t term accounts for forming or applying threshold masks, child-label slices, label copies, and shuffles for each observed or permuted draw. Under splitter early stopping, threshold ordering has two paths. If threshold scanning is enabled, it uses weighted child impurity as an ordering score and adds $O(h_t(C^{\text{split}}(n_t) + n_t) + h_t \log h_t)$. If threshold scanning is disabled, the retained thresholds are still randomly permuted, adding $O(h_t)$. These ordering steps are separate from the permutation p -value computation.

Finally, if Stage B accepts a split and the impurity decrease is large enough, the dense matrix tree builder creates left and right child matrices with all p columns. This copy costs $O(n_t p)$. Nodes that reach Stage A but become leaves because Stage A or Stage B does not reject still incur the

work already described. Terminal leaves can also occur when constant feature pruning leaves no available feature, threshold generation or leaf size filtering leaves no valid threshold, or an accepted threshold fails the minimum impurity-decrease gate. These leaves contribute the costs incurred up to that point but do not allocate child matrices.

Fixed- B and adaptive modes. In the exhaustive fixed- B reference setting, Stage A tests every feature in F_t , Stage B tests every retained threshold, and both stages use fixed permutation budgets. In adaptive runs, stopping can reduce work by testing fewer features or thresholds or using fewer permutation draws. Feature and threshold scanning are ordering heuristics: they pay for a prescan so likely features or thresholds are tried earlier. They can reduce realized runtime when the shorter stopping path offsets the prescan work, but they do not improve the worst-case bound because the stopping rule can still examine all features or thresholds and use the full budget.

From nodes to trees and forests. Let W_t be the cost paid at node t : the stopping checks, any Stage A work, any Stage B work, and any child-copy work reached by the builder. Tree training cost is the sum over all realized tree nodes, not only over internal split nodes:

$$T_{\text{tree}} = \sum_{t \in \mathcal{V}(\mathcal{T})} W_t. \quad (22)$$

Here $\mathcal{V}(\mathcal{T})$ and $\mathcal{I}(\mathcal{T})$ are the realized node set and internal split-node set. Leaves stopped by the initial checks contribute only the stopping and value computation term at that node, while leaves that fail after Stage A or Stage B contribute the corresponding testing terms. A binary tree has $|\mathcal{V}(\mathcal{T})| = 2|\mathcal{I}(\mathcal{T})| + 1$. A depth cap gives a coarse exponential node count bound, but n_t , a_t , m_t , $\tilde{h}_t$, h_t , and the realized permutation counts usually change with depth.

If honesty is enabled, the node sum is computed on the structure building subsample. Training also pays $O(np)$ for the dense split/estimation partition and a leaf re-estimation pass. If e is the estimation-sample size and ℓ_i is the fitted-tree path length for estimation sample i , the current tuple-based path representation gives worst-case routing cost $O(\sum_{i=1}^e \ell_i^2)$, followed by a stored-path tree walk of $O(\sum_{v \in \mathcal{V}(\mathcal{T})} d_v + e)$, where d_v is node depth.

For a forest of M trees, let s_r be the number of samples used to fit tree r after bootstrap and classifier sampling. Let C_r^{sample} be the cost of constructing those sample indices. Row selection and per-tree dense validation/copy add $O(s_r p)$ before tree growth. The forest fit first validates the full input and then fits the trees. Write $T_{\text{tree},r}$ for the node-sum cost of tree r computed as above. The total computational work of the forest fit, before parallel wall-clock scheduling effects, can be summarized as

$$T_{\text{forest}} = O(np) + \sum_{r=1}^M \left(C_r^{\text{sample}} + O(s_r p) + T_{\text{tree},r} + \mathbf{1}_{\text{honest}} H_{\text{honest},r} \right) + O(Mp) + \mathbf{1}_{\text{oob}} T_{\text{oob}}, \quad (23)$$

where $\mathbf{1}_{\text{honest}}$ is one when honesty is enabled and zero otherwise, $H_{\text{honest},r}$ denotes the honesty partition and leaf re-estimation cost just described for tree r , $\mathbf{1}_{\text{oob}}$ is one when OOB scoring is requested and zero otherwise, and T_{oob} is the optional post-fit OOB scoring cost, separate from the tree-building sum. With joblib parallelism, wall-clock time depends on the effective worker count, load balance across trees, process overhead, and memory bandwidth; the expression above is a work accounting.

Without bootstrap sampling, each tree starts with root size n and the bootstrap cap is unused. With bootstrap sampling, the configured bootstrap sample-size parameter sets the requested sample size or an upper bound, and classifier sampling can reduce s_r further. If honesty is enabled, the root size for structure building is the splitting subsample size.

Memory accounting. At a node, feature index arrays and scanning arrays use $O(a_t + m_t)$ space, and threshold construction uses $O(n_t + \tilde{h}_t + h_t)$ auxiliary space. Permutation tests add workspaces for statistics, masks, labels, permutation outputs, and selector-specific arrays. Fixed-budget non-adaptive tests may store an $O(B_{\text{stage}})$ vector of permuted statistics, where B_{stage} is the configured fixed budget for the selector or splitter test being run. Adaptive paths can keep constant-size counters apart from copied or shuffled labels and selector-specific arrays.

The dense matrix terms dominate in many fits. Validation materializes a dense $O(np)$ feature matrix. Each accepted split materializes dense left and right child matrices with all p columns and combined size $O(n_t p)$. During depth-first recursion, parent frames retain sibling child arrays while one child is being grown. If $\mathcal{P}$ is the set of accepted split nodes whose child matrices are live on the active recursion stack, the dense-array part of peak single-tree training memory is bounded by

$$O\left(np + p \sum_{u \in \mathcal{P}} n_u\right),$$

plus node-local auxiliary workspaces. This is a live-path bound: it is $O(np)$ for balanced growth but can be larger for highly unbalanced recursion.

Honesty adds memory during fitting for the dense split and estimation partitions. It also stores estimation-sample groups by leaf path, giving $O(e + \sum_{q \in \mathcal{Q}} |q|)$ path-index workspace for the set $\mathcal{Q}$ of retained leaf-path keys, bounded by $O(eD)$ when all estimation samples have path length at most D . This is in addition to the tree-building memory above.

Forest peak training memory grows with concurrent tree fits. Let $w = \min(M, n_{\text{jobs}})$, where n_{jobs} is the number of parallel jobs used by the joblib backend after parameter normalization. Peak memory includes the validated forest input, returned estimators, and up to w concurrently executing per-tree workspaces: bootstrap indices, dense row-selected matrices, validation copies, and peak memory terms for each tree. Depending on joblib serialization or memmap behavior, workers may also hold shared memmaps or copies of the validated input.

For the same M -tree forest, fitted storage includes stored node records for all trees, the estimator list, $O(Mp)$ per-tree arrays such as feature names and feature importances, and $O(p)$ forest-level metadata arrays. If OOB scoring is enabled, fitted storage also includes $O(nK)$ classifier OOB decision values for K classes or $O(n)$ regressor OOB predictions, plus the scalar OOB score. OOB scoring also uses temporary workspace during fitting for the OOB count vector, recomputed bootstrap and unsampled indices, prediction slices X_{oob} , and per-tree predictions or class-probability arrays.

Appendix F Datasets

F.1 Benchmark datasets

The dataset inventory covers the real-data benchmark and the synthetic feature-recovery analyses. For each real-data benchmark dataset, the tables report the number of samples n , the number of features p , and the source collection. Source labels refer to UCI Machine Learning Repository [22], the NIPS 2003 feature selection challenge [13], ASU/scikit-feature [25], OpenML [41], and CoEPrA molecular-property benchmarks [7]. ASU/SF abbreviates ASU/scikit-feature. Slash-separated labels indicate original benchmark provenance and OpenML availability or hosting.

Dataset	n	p	Source
gamma	19,020	9	UCI
glass	214	10	UCI
page-blocks	5,473	10	UCI
vowel-context	990	10	UCI
wine	178	13	UCI
letter	20,000	16	UCI
pendigits	10,992	16	UCI
spam	4,601	57	UCI
musk	6,597	166	UCI
madelon	2,000	500	NIPS 2003
isolet	7,797	616	UCI
ORL	400	1,024	ASU/SF
Yale	165	1,024	ASU/SF
warpAR10P	130	2,400	ASU/SF
warpPIE10P	210	2,420	ASU/SF
gisette	6,000	5,000	NIPS 2003
TOX_171	171	5,748	ASU/SF
ALLAML	72	7,129	ASU/SF
arcene	100	10,000	NIPS 2003
pixraw10P	100	10,000	ASU/SF
orlraws10P	100	10,304	ASU/SF
CALL_SUB_111	111	11,340	ASU/SF
dexter	300	20,000	NIPS 2003

Table 13: Classification benchmark datasets.

Dataset	n	p	Source
facebook	500	21	UCI/OpenML
imports-85	205	76	UCI
residential	372	107	UCI/OpenML
community_crime	1,994	1,954	UCI/OpenML
comm_violence	2,215	2,210	UCI/OpenML
coepra2	76	5,144	CoEPrA/OpenML
coepra1	89	5,787	CoEPrA/OpenML
coepra3	133	5,787	CoEPrA/OpenML

Table 14: Regression benchmark datasets.

F.2 Synthetic datasets

These tables report n , p , and key settings for each synthetic feature-recovery design. In the classification table, **sep** denotes class separation and **flip** denotes label-flip probability. In the regression table, **noise** denotes the response-noise scale; for the heteroscedastic row, **scale** controls the feature-dependent noise multiplier.

The synthetic datasets are controlled recovery problems with known informative features. The classification designs cover redundant features, high-cardinality noise, nonlinear signal, standard and weak signal, Toeplitz correlation, correlated-noise features, and sparse high- p structure. The regression designs cover heteroscedastic noise, redundant features, Friedman 1, standard and weak signal, Toeplitz correlation, correlated-noise features, and sparse high- p structure. The settings keep the examples compact while including one high-dimensional, small-sample case for each task.

Design	Setting	n	p
Redundant features	10 informative, 20 redundant features	1,000	50
High-cardinality noise	10 informative, 50 high-cardinality noise features, 500 levels	1,000	100
Nonlinear signal	binarized Friedman 1, 5 informative	1,000	100
Standard classification	10 informative, sep = 2.0	1,000	100
Toeplitz correlation	10 informative, $\rho = 0.95$	1,000	100
Weak signal classification	10 informative, sep = 0.1, flip = 0.1	1,000	100
Correlated noise	10 informative, 20 added correlated-noise features, $\rho = 0.9$	1,000	120
Sparse high- p classification	5 informative, sep = 0.5	200	1,000

Table 15: Synthetic classification designs used in the feature-recovery analysis.

Design	Setting	n	p
Heteroscedastic regression	heteroscedastic scale = 4.0, noise = 5.0	1,000	50
Redundant features	10 informative, 20 redundant features	1,000	50
Friedman 1	5 informative, noise = 1.0	1,000	100
Standard regression	10 informative, noise = 1.0	1,000	100
Toeplitz correlation	10 informative, $\rho = 0.95$	1,000	100
Weak signal regression	10 informative, noise = 50.0	1,000	100
Correlated noise	10 informative, 20 added correlated-noise features, $\rho = 0.9$	1,000	120
Sparse high- p regression	5 informative, noise = 10.0	200	500

Table 16: Synthetic regression designs used in the feature-recovery analysis.

Appendix G Benchmark stability

The benchmark-stability checks report dataset counts, complete-case CIF comparisons, leave-one-dataset-out (LODO) configuration sensitivity, and sensitivity checks by downstream learner, standard values of k , and seed. Table 17 summarizes the dataset counts used by the benchmark analyses. Counts differ because each analysis is restricted to the datasets, downstream learners, and standard top- k values available for that comparison. The main real-data counts are unique datasets with at least one complete learner-by- k combination for all methods; the complete-case analyses below use the stricter set with every standard learner-by- k combination present.

Analysis	Classification datasets	Regression datasets	Purpose
Main real-data comparison	21	8	Primary rank summary on real datasets
Complete-case CIF and rank checks	13	6	Bootstrap intervals and omnibus rank summaries
LODO configuration sensitivity	13	6	Held-out-dataset configuration checks
Learner $\times k$ sensitivity	21, 20, 14, 14, 13	8, 8, 7, 7, 6	Method ordering by downstream learner and value of k
Seed sensitivity	13	6	Seed variation on datasets complete across seeds

Table 17: Dataset counts for benchmark analyses. The learner-by- k row lists counts at $k = 5, 10, 25, 50, 100$; each summary uses the datasets, downstream learners, and standard top- k values available for its comparison.

G.1 Bootstrap and rank checks

Table 18 gives complete-case CIF comparisons against ctree, cforest, and CIT after restricting to datasets with all methods, downstream learners, and all five standard top- k values available. Within each task, all comparisons use the same datasets, the same downstream learners, and $k \in \{5, 10, 25, 50, 100\}$.

Task	Compared method	Mean Δ	95% CI	W-L
Classification	ctree	0.049	[0.026, 0.073]	11-2
Classification	cforest	0.013	[0.002, 0.024]	9-4
Classification	CIT	0.044	[0.027, 0.062]	13-0
Regression	ctree	0.202	[0.029, 0.421]	4-2
Regression	cforest	0.027	[-0.032, 0.090]	5-1
Regression	CIT	0.308	[-0.002, 0.766]	5-1

Table 18: Complete-case CIF differences against ctree, cforest, and CIT. Mean Δ is CIF minus comparator after averaging each dataset over the same downstream learners and values of k . Intervals resample dataset-level paired deltas with 20,000 percentile-bootstrap replicates. W-L gives dataset-level wins and losses; no exact ties occurred.

The metric is balanced accuracy for classification and R^2 for regression. Positive differences favor CIF. The intervals summarize dataset-level paired deltas after configuration selection. Large positive regression differences can reflect negative mean R^2 for the comparator.

The Friedman checks use dataset-level method means after averaging the 15 learner-by- k combinations. Classification (13 datasets): $\chi^2(16) = 140.46$, $p < 0.001$, Kendall’s $W = 0.68$. Regression (6 datasets): $\chi^2(17) = 26.15$, $p = 0.072$, Kendall’s $W = 0.26$, which does not reach the 0.05 level; the regression rank ordering is therefore a descriptive summary of this panel.

G.2 LODO configuration sensitivity

Table 19 reports LODO configuration selection for each task. Each run selects configurations on all but one complete-case dataset in that task, evaluates the held-out dataset, and averages scores and ranks over downstream learners and standard top- k values. CIF reselects the main-benchmark configuration in 11 of the 13 classification holdouts, using 2 distinct configurations. In regression, it also uses two configurations, reselects the global regression configuration in 4 of 6 holdouts, and is sixth by mean LODO rank behind ExtraTrees, CatBoost, RF-RFE, RF, and RT.

G.3 Breakdowns by downstream learner, top- k value, and seed

The main benchmark averages over downstream learners, standard values of k , folds, and seeds. The next tables show how method ordering changes when results are split by downstream learner, value of k , and seed. They use the same selected method configurations as the main benchmark.

For the learner and k checks, one unit is one downstream learner paired with one standard value of k . Within each unit, methods are ordered by mean rank among datasets where every benchmark method is available for that learner-by- k combination; ties use average ranks. Tables 20 and 21 show all 15 learner-by- k combinations for each task. Rows follow the main benchmark order. The learner columns report mean position over the five standard values of k for that learner; lower positions are better. Mean position averages the positions obtained after ordering methods within each learner-by- k combination; mean rank averages the dataset-level ranks directly. Top 3 of 15 and Top 5 of 15 count the learner-by- k combinations where the method ranks in the top 3 or top 5.

Classification					Regression				
Method	Rank	Score	Settings	Main	Method	Rank	Score	Settings	Main
RF-RFE	2.54	0.825	1	13/13	ExtraTrees	4.67	0.292	1	6/6
LightGBM	4.31	0.813	1	13/13	CatBoost	6.17	0.229	1	6/6
RF	5.08	0.802	1	13/13	RF-RFE	6.67	0.333	1	6/6
CatBoost	5.54	0.801	1	13/13	RF	6.83	0.260	1	6/6
XGBoost	5.69	0.808	2	11/13	RT	7.00	0.266	1	6/6
Boruta	6.23	0.791	1	13/13	CIF	7.33	0.240	2	4/6
ExtraTrees	6.62	0.792	1	13/13	XGBoost	8.50	0.149	2	5/6
CIF	6.85	0.793	2	11/13	DT	8.67	0.124	1	6/6
cforest	8.23	0.785	1	13/13	Boruta	9.17	0.118	1	6/6
DT	9.38	0.763	1	13/13	LightGBM	10.50	-0.214	1	6/6
RDC filter	10.69	0.764	1	13/13	CIT	10.67	-0.206	2	5/6
ctree	11.77	0.749	1	13/13	cforest	10.67	0.092	2	5/6
CIT	12.15	0.754	1	13/13	PI	11.00	-0.024	1	6/6
MC filter	12.69	0.737	1	13/13	ctree	11.33	0.051	1	6/6
RT	13.00	0.737	1	13/13	PC filter	11.67	0.099	1	6/6
PI	15.73	0.676	1	13/13	RDC filter	12.50	-0.082	1	6/6
CPI	16.50	0.600	1	13/13	DC filter	13.50	-0.009	1	6/6
					CPI	14.17	-0.554	1	6/6

Table 19: LODO configuration sensitivity. Lower rank is better; rows are ordered by mean LODO rank within each task. Score is the mean held-out metric. Settings reports the number of distinct selected configurations; Main reports how often the main benchmark configuration is reselected. Ranks are computed within held-out datasets before averaging, so score order need not match rank order.

Method	KNN	LR	SVM	Mean position	Mean rank	Best-worst	Top 3 of 15	Top 5 of 15
RF-RFE	1.7	5.0	1.8	2.8	5.2	1.0–8.0	10/15	13/15
XGBoost	5.4	2.7	3.4	3.8	5.8	2.0–8.0	9/15	11/15
CIF	4.2	4.4	5.7	4.8	6.7	2.0–7.0	3/15	10/15
RF	3.6	5.1	5.1	4.6	6.4	1.5–7.0	3/15	10/15
LightGBM	4.2	2.2	2.0	2.8	5.5	1.0–6.0	11/15	13/15
Boruta	5.2	8.6	7.8	7.2	7.5	1.0–9.0	2/15	2/15
CatBoost	6.1	3.4	4.1	4.5	6.3	1.0–8.0	5/15	10/15
ExtraTrees	6.8	7.6	8.8	7.7	7.7	2.0–12.0	1/15	1/15
cforest	9.5	7.6	9.3	8.8	8.2	5.0–11.0	0/15	1/15
DT	10.4	9.2	8.4	9.3	9.5	4.0–13.5	0/15	2/15
RDC filter	11.2	12.0	12.6	11.9	10.8	10.0–15.0	0/15	0/15
PI	15.3	15.8	15.8	15.6	13.4	13.5–16.0	0/15	0/15
MC filter	12.0	13.6	13.8	13.1	11.3	10.0–17.0	0/15	0/15
RT	15.0	13.0	13.5	13.8	11.9	10.0–16.0	0/15	0/15
ctree	12.1	13.0	12.4	12.5	11.0	10.0–15.0	0/15	0/15
CIT	13.3	12.8	11.7	12.6	11.0	9.0–16.0	0/15	0/15
CPI	17.0	17.0	16.8	16.9	14.8	16.0–17.0	0/15	0/15

Table 20: Classification sensitivity by downstream learner and value of k . Lower values are better. KNN, LR, and SVM denote downstream learners; Top 3 of 15 and Top 5 of 15 count the learner-by- k combinations where the method ranks in the top 3 or top 5. Mean position averages ordinal method positions over the 15 combinations; mean rank averages the underlying dataset-level ranks. The dataset counts at $k = 5, 10, 25, 50, 100$ are 21, 20, 14, 14, and 13.

In the classification learner-by- k sensitivity table, CIF is top five in 10 of the 15 learner-by- k combinations and top three in 3 of 15. Its mean position is close to RF’s and is better than the single-tree and filter baselines in the mean-position summary. RF-RFE, LightGBM, XGBoost, and CatBoost have lower mean positions.

Method	KNN	Ridge	SVR	Mean position	Mean rank	Best–worst	Top 3 of 15	Top 5 of 15
ExtraTrees	6.2	2.4	2.6	3.7	6.8	1.0–11.0	9/15	11/15
CIF	4.6	9.9	2.4	5.6	7.8	1.0–12.0	7/15	8/15
CatBoost	2.0	8.9	3.2	4.7	7.3	1.0–15.0	6/15	12/15
RF-RFE	3.2	3.0	5.9	4.0	7.1	1.0–9.0	7/15	11/15
RF	7.8	4.2	10.0	7.3	8.3	2.0–13.0	2/15	4/15
RT	4.4	10.0	6.1	6.8	8.5	2.0–17.0	3/15	7/15
cforest	11.4	11.7	9.9	11.0	10.1	6.0–16.0	0/15	0/15
DT	6.7	9.4	9.1	8.4	9.0	4.0–16.0	0/15	2/15
Boruta	12.5	4.4	11.9	9.6	9.4	2.0–16.0	2/15	2/15
PC filter	12.8	12.0	11.0	11.9	10.7	8.0–16.0	0/15	0/15
LightGBM	9.2	10.4	9.8	9.8	9.6	1.0–17.0	3/15	3/15
XGBoost	6.5	15.9	9.3	10.6	9.9	1.5–18.0	1/15	4/15
RDC filter	14.3	10.1	6.5	10.3	9.8	3.0–16.0	1/15	2/15
CIT	14.7	12.4	14.7	13.9	11.0	8.5–18.0	0/15	0/15
ctree	8.2	9.2	17.4	11.6	10.9	1.0–18.0	2/15	4/15
PI	12.3	7.1	14.4	11.3	10.2	3.0–16.0	1/15	2/15
DC filter	16.4	13.9	9.6	13.3	11.1	7.0–17.0	0/15	0/15
CPI	17.8	16.1	17.2	17.0	13.6	9.5–18.0	0/15	0/15

Table 21: Regression sensitivity by downstream learner and value of k . Lower values are better. KNN, Ridge, and SVR denote downstream learners; Top 3 of 15 and Top 5 of 15 count the learner-by- k combinations where the method ranks in the top 3 or top 5. Mean position averages ordinal method positions over the 15 combinations; mean rank averages the underlying dataset-level ranks. The dataset counts at $k = 5, 10, 25, 50, 100$ are 8, 8, 7, 7, and 6.

CIF has the fourth-lowest regression mean position in this breakdown, after ExtraTrees, RF-RFE, and CatBoost, and remains ahead of ctree, cforest, CIT, and most filter and wrapper methods in this summary. The pairwise figures use the datasets available for each comparator; the complete-case panels above use the 13/6 all-method dataset sets.




Figure 6: Classification CIF margins against ctree, cforest, and CIT by downstream learner and value of k . Each plotted value is the mean balanced-accuracy difference, CIF minus comparator, for one downstream learner and one value of k ; positive values favor CIF. Dataset counts by k are 21, 20, 14, 14, and 13 for ctree, 22, 21, 15, 15, and 14 for cforest, and 23, 22, 16, 16, and 15 for CIT.




Figure 7: Regression CIF margins against ctrees, cforest, and CIT by downstream learner and value of k . Each plotted value is the mean R^2 difference, CIF minus comparator, for one downstream learner and one value of k ; positive values favor CIF. Dataset counts by k are 8, 8, 7, 7, and 6 for each comparison. Large positive plotted values can reflect negative mean R^2 for the comparator. Numeric labels show the unclipped values; the color scale is clipped at ± 1 for readability.

For the seed checks, each method is ranked separately within each fixed seed. Keeping only datasets with results for every method, downstream learner, standard top- k value, and seed leaves 13 classification datasets and 6 regression datasets complete across all five seeds. These tables summarize seed variation by rank without intervals or tests. In these tables, a seed column is the method’s ordinal position after sorting that seed’s averaged dataset-level ranks, while mean rank is the averaged dataset-level rank value itself. Rows follow the main benchmark order.

Method	Seed 1	Seed 2	Seed 3	Seed 4	Seed 5	Mean position	Mean rank
RF-RFE	1	1	1	1	1	1.0	4.9
XGBoost	2	4	2	3	3	2.8	5.8
CIF	6	5	6	5	7	5.8	6.9
RF	5	6	4	6	4	5.0	6.6
LightGBM	3	2	3	2	2	2.4	5.6
Boruta	7	7	8	7	8	7.4	7.6
CatBoost	4	3	5	4	5	4.2	6.4
ExtraTrees	8	8	7	8	6	7.4	7.5
cforest	9	9	9	9	9	9.0	8.3
DT	10	10	11	10	10	10.2	9.6
RDC filter	11	11	12	13	12	11.8	10.4
PI	16	16	16	16	16	16.0	14.2
MC filter	13	14	14	14	15	14.0	11.1
RT	15	15	15	15	14	14.8	11.6
ctree	14	12	10	12	11	11.8	10.4
CIT	12	13	13	11	13	12.4	10.5
CPI	17	17	17	17	17	17.0	15.7

Table 22: Classification seed sensitivity on the 13 datasets complete across all five seeds. Each seed column is the method’s ordinal position after sorting methods by their averaged dataset-level ranks for that seed. Mean position averages those five ordinal positions; mean rank reports the averaged dataset-level rank value itself. Lower values are better.

Method	Seed 1	Seed 2	Seed 3	Seed 4	Seed 5	Mean position	Mean rank
ExtraTrees	3	2	3	3	3	2.8	7.4
CIF	6	5	8	8	4	6.2	8.6
CatBoost	2	7	4	1	1	3.0	7.4
RF-RFE	1	1	1.5	4	2	1.9	7.2
RF	5	3	5	7	7	5.4	8.5
RT	4	4	1.5	5	6	4.1	8.2
cforest	15	13	13	12	11	12.8	10.2
DT	14	6	7	2	5	6.8	8.6
Boruta	9	10	10	11	8	9.6	9.3
PC filter	16	16	15	14	16	15.4	11.3
LightGBM	8	9	9	10	10	9.2	9.3
XGBoost	7	8	11	6	12	8.8	9.2
RDC filter	10	14	14	13	14	13.0	10.4
CIT	12	12	17	17	9	13.4	10.7
ctree	13	15	12	15	13	13.6	10.6
PI	11	11	6	9	15	10.4	9.7
DC filter	17	17	16	16	17	16.6	11.9
CPI	18	18	18	18	18	18.0	12.8

Table 23: Regression seed sensitivity on the 6 datasets complete across all five seeds. Each seed column is the method’s ordinal position after sorting methods by their averaged dataset-level ranks for that seed; fractional positions indicate ties. Mean position averages those five ordinal positions; mean rank reports the averaged dataset-level rank value itself. Lower values are better.

Appendix H Feature use in sampled forests

The extended p -sweep expands the main-text feature-sampling analysis, separate from the benchmark-stability summaries in Appendix G. Figures 8 and 9 show feature-sampling results for $p \in \{100, 500, 1,000\}$. Each forest uses 1,000 trees, with classification and regression shown separately. For each method and feature dimension p , each point is the mean over $n_{\text{informative}} \in \{1, 2, 5, 10\}$, and the capped bar spans the minimum and maximum over those four sparse settings.

In classification, evaluating all nonconstant features at each split gives the largest informative-feature gains in sparse high- p settings. CIF-all keeps feature muting and the other tree settings unchanged while removing feature subsampling. With two informative features and $p=100$, CIF uses informative features in 40.0% of splits, while CIF-all does so in 100.0%. The corresponding values are 12.2% versus 90.2% at $p=500$ and 9.0% versus 100.0% at $p=1,000$. CIF-all also uses 70, 264, and 439 fewer distinct uninformative features than CIF. With five informative features, the CIF-all minus CIF differences are 25.1, 56.4, and 54.3 percentage points at $p=100$, $p=500$, and $p=1,000$.

Regression shows a similar informative-feature use pattern in the one- and two-informative-feature settings, and CIF-all also uses more distinct uninformative features. With two informative features and $p=100$, CIF uses informative features in 39.9% of splits, while CIF-all does so in 58.8%. The corresponding values are 19.7% versus 46.7% at $p=500$ and 11.6% versus 35.9% at $p=1,000$. With one informative feature, the CIF-all minus CIF differences are 29.8, 18.9, and 42.1 percentage points.




Figure 8: Classification forest feature sampling by feature dimension p with 1,000 trees per fit. Points are means over $n_{\text{informative}} \in \{1, 2, 5, 10\}$; capped bars span the minimum-to-maximum values across those four sparse designs. (A) shows % of splits using informative features; (B) shows the number of distinct uninformative features used.




Figure 9: Regression forest feature sampling by feature dimension p with 1,000 trees per fit. Points are means over $n_{\text{informative}} \in \{1, 2, 5, 10\}$; capped bars span the minimum-to-maximum values across those four sparse designs. (A) shows % of splits using informative features; (B) shows the number of distinct uninformative features used.